

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-075-10019-00-00  
Spot: SWNE Sec/Twnshp/Rge: 31-21S-41W  
3294 feet from S Section Line, 2023 feet from E Section Line  
Lease Name: HCU (HATFIELD 1) Well #: 3111  
County: HAMILTON Total Vertical Depth: 2805 feet

Operator License No.: 33999  
Op Name: LINN OPERATING, INC.  
Address: 600 TRAVIS STE 5100  
HOUSTON, TX 77002

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		1200		
PROD	4.5	2798	0	WITH 100 SX CMT
SURF	8.625	139		WITH 125 SX CMT

Well Type: OG UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/01/2016 9:00 AM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING

Plugging Proposal Received By: KEN JEHLIK WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 11/03/2016 12:30 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

Perfs:

2 7/8" TBG & PACKER AT 2704' INSIDE 4 1/2" CASING. 1 1/4" TBG INSIDE 2 7/8" TBG. PULL 1/2" RODS & FISH PARTED 1 1/4" TBG. PACKER IS STUCK. 11/2/16: CUT TBG AT 2350'. LEFT 350' OF 2 7/8" TBG & PACKER IN WELL. SPOT 50 SX CMT WITH 50# HULLS AT 2319'. 11/3/16: CIBP @ 1200'. PERFORATE 4 HOLES AT 1175'. RUN TBG & PACKER TO 745'. INJECTION RATE 2 BPM @ 400#. PUMP 50 SX CMT WITH 25# HULLS IN LAST 25 SX CMT. DISPLACE TO 800' LEAVING 25 SX CMT INSIDE THE CASING & 25 SX CMT OUTSIDE THE CASING. PERFORATE 4 HOLES AT 300'. RUN TBG & PACKER TO 225' & CIRCULATE CMT FROM 300' TO SURFACE IN THE 4 1/2" X 8 5/8" ANNULUS WITH 80 SX CMT. RELEASE PACKER & CIRCULATE CMT TO SURFACE FROM 300' TO SURFACE INSIDE THE 4 1/2" CASING WITH 80 SX CMT.

Top	Bot	Thru	Comments
2756	2757		

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY WELL SERVICE.

Plugged through: TBG

District: 01

Signed

*Ken Jehlik*  
JA

(TECHNICIAN)

RECEIVED  
NOV - 7 2016  
KCC DODGE CITY  
*MR*

NOV 21 2016  
720  
Form CP-2/3