

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-075-10022-00-00
Spot: SENE SW Sec/Twnshp/Rge: 16-22S-41W
1964 feet from S Section Line, 3270 feet from E Section Line
Lease Name: HCU (KITTEN 1) Well #: 1621
County: HAMILTON Total Vertical Depth: 2747 feet

Operator License No.: 33999
Op Name: LINN OPERATING, INC.
Address: 600 TRAVIS STE 5100
HOUSTON, TX 77002

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		1200		
PROD	4.5	2745	0	WITH 100 SX CMT
SURF	8.625	178		WITH 150 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 10/31/2016 10:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 10/31/2016 7:30 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

Perfs:

PUMP 20 SX CMT WITH 75# HULLS AT 2717' THOROUGH TBG. CUT STUCK PACKER (2303') AT 2275'. SPOT 20 SX CMT PLUG AT 2275'. SET CIBP @ 1200'. ATTEMPT TO TEST CASING. WOULD NOT TEST. PERFORATE 4 HOLES AT 1150'. RUN TBG & PACKER TO 750'. INJECTION RATE INTO PERFS AT 2 BPM AT 450#. SPOT 50 SX CMT AT 1150', LEAVING 25 SX CMT OUTSIDE THE CASING AND 25 SX CMT WITH HULLS INSIDE THE CASING. PERFORATE 4 HOLES AT 300'. CIRCULATE CMT TO SURFACE WITH 100 SX CMT


Top	Bot	Thru	Comments
2717	2724		

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY.

Plugged through: TBG

District: 01

Signed


SA

(TECHNICIAN)

RECEIVED
NOV - 7 2016
KCC DODGE CITY

NOV 21 2016 Form CP-2/3