

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-075-10028-00-00
Spot: SENW Sec/Twnshp/Rgc: 4-22S-41W
3288 feet from S Section Line, 3319 feet from E Section Line
Lease Name: HCU (TROUP 04-21) Well #: 0421
County: HAMILTON Total Vertical Depth: 2783 feet

Operator License No.: 33999
Op Name: LINN OPERATING, INC.
Address: 600 TRAVIS STE 5100
HOUSTON, TX 77002

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		2660		
PROD	4.5	2783	0	WITH 100 SX CMT
SURF	8.625	168		WITH 125 SX CMT

Well Type: OG UIC Docket No: _____ Date/Time to Plug: 10/19/2016 10:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: KEN JEHLIK WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 10/19/2016 2:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

Perfs:

****CASING LEAKS SQUEEZED FROM 1185' TO 1336'.** CIBP @ 2660'. RAN CBL FROM 1630' TO 200' OVER THE INTERVAL WHERE CASING LEAKS ARE SQUEEZED. FOUND CMT COVERAGE FROM 1550' TO 700'. PERFORATE 4 HOLES AT 300'. RAN TBG TO 2400' & SPOTTED 20 SX CMT PLUG. PULL TO 1200' & CIRCULATE CMT TO SURFACE UP THE 4 1/2" CASING & 4 1/2" X 8 5/8" ANNULUS SIMULTANEOUSLY USING 175 SX CMT.**

Top	Bot	Thru	Comments
2765	2770		

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY.

Plugged through: TBG

District: 01

Signed



(TECHNICIAN)

RECEIVED
OCT 31 2016
KCC DODGE CITY

NOV 21 2016
710

Form CP-2/3