

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-023-21450-00-00  
Spot: NESWNWNE Sec/Twshp/Rge: 16-5S-37W  
663 feet from N Section Line, 2121 feet from E Section Line  
Lease Name: WAILES FARMS, INC. Well #: 1-16  
County: CHEYENNE Total Vertical Depth: 5057 feet

Operator License No.: 6039  
Op Name: L. D. DRILLING, INC.  
Address: 7 SW 26TH AVE  
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4832		180 SX
SURF	8.625	421		375 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/30/2016 9:00 AM  
Plug Co. License No.: 34787 Plug Co. Name: GREEN OIL FIELD SERVICES, LLC  
Proposal Rcvd. from: MIKE KASSELMAN Company: L D DRILLING Phone: (620) 793-3051

Proposed Plugging Method: Ordered 500 sx 60/40 pozmix 4% gel cement, 1200 # gel and 750 # hulls.  
8 5/8" surface casing set at 421' w/375 sx cement.  
5 1/2" production casing set at 4832' w/180 sx cement.  
TD 5057'. PBSD 4832'.  
Perforations: 4686' - 4688'.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 09/30/2016 5:00 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

Perforated production casing at 3156' and 2265'. Ran in hole with tubing to 4600'. Pumped 1200 # gel followed by 60 sx cement w/40 # hulls. Pump truck was not capable of pumping hulls. TOOH with tubing to 3150' and pumped 155 sx cement w/150 # hulls. TOOH with tubing to 1575' and pumped 150 sx cement w/60 # hulls. Bulk truck compressor broke down. Manually controlled pop off valve. Pumped 5 sx cement. Cement circulated to surface. TOOH with tubing to surface. Connected to 5 1/2" production casing and pumped 20 sx cement. Casing full. Connected to 8 5/8" surface casing and pumped 60 sx cement. Shut in pressure 230 psi.

Perfs:

Top	Bot	Thru	Comments
4686	4688		

Remarks: GREEN OILFIELD SERVICES LLC PULLING UNIT AND BASIC ENERGY SERVICES TICKET # 751008C

Plugged through: TBG

District: 04

Signed Darrel Dipman  
KCC WICHITA (TECHNICIAN)

OCT 31 2016

NOV 21 2016

CM

OCT 03 2016

RECEIVED

*MD*

Form CP-2/3