

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-051-22533-00-00
Spot: SWNWNENE Sec/Twnshp/Rge: 35-11S-20W
360 feet from N Section Line, 1130 feet from E Section Line
Lease Name: CONNELL Well #: 1-35
County: ELLIS Total Vertical Depth: 3820 feet

Operator License No.: 30606
Op Name: MURFIN DRILLING CO., INC.
Address: 250 N WATER STE 300
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3819		175 SX
SURF	8.625	202		160 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/18/2016 9:00 AM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: CRAIG HERTEL Company: MURFIN DRILLING CO., INC. Phone: (785) 623-0123

Proposed Plugging Method: Ordered 445 sx 60/40 pozmix 4% gel cement w/500 # hulls.
DV Tool at 2723' w/482 sx cement.
1 joint of tubing and anchor at 3707' stuck in hole.
Rods tops at 3146'.
Perforations: 3718' - 3724', 3705' - 3710', 3710' - 3712' and 3731' - 3733'

Plugging Proposal Received By: PAT STAAB Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 10/18/2016 11:45 AM KCC Agent: PAT STAAB

Actual Plugging Report:

Murfin ran in hole with tubing to 3127'. Hurricane Cementing rigged to tubing and pumped 100 sx cement w/300 # hulls mixed in. Pulled tubing to 2046'. Rigged to tubing and pumped 237 sx cement w/200 # hulls mixed in to circulate cement to surface. Pulled tubing. Rigged to 5 1/2' casing with a swedge and pumped 25 sx cement at 200 psi. Shut in pressure 200 psi. Rigged to 8 5/8" surface casing and pumped 20 sx cement at 200 psi. Shut in pressure 200 psi.

GPS: 39.05849 -099.550514

Perfs:

Top	Bot	Thru	Comments
3731	3733		
3718	3724		
3710	3712		
3705	3710		

Remarks: HURRICANE CEMENTING CO. TICKET # 100692

Plugged through: TBG

District: 04

Signed _____

(TECHNICIAN)

KCC WICHITA

OCT 31 2016

RECEIVED

NOV 21 2016

Form CP-2/3

OCT 21 2016