

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-097-21479-00-00
Spot: SESW Sec/Twnshp/Rge: 6-28S-17W
585 feet from S Section Line, 3100 feet from E Section Line
Lease Name: KELLER Well #: A-2
County: KIOWA Total Vertical Depth: 4850 feet

Operator License No.:	31881	String	Size	Depth (ft)	Pulled (ft)	Comments
Op Name:	<u>MCGINNESS OIL COMPANY OF KANSAS</u>	PROD	4.5	4849	2436	WITH 175 SX CMT
Address:	<u>1700 N WATERFRONT PKWY, BLDG. 3</u> <u>WICHITA, KS 67206</u>	SURF	8.625	420		WITH 225 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 10/31/2016 8:30 AM
Plug Co. License No.: 34227 Plug Co. Name: AMERICAN WELL SERVICE LLC
Proposal Rcvd. from: KEITH BRIGHT Company: MCGINNESS OIL COMPANY Phone: (316) 239-8593

Proposed Plugging Method: SQUEEZE PERFS WITH 2 SX CMT WITH 100# HULLS. PLUG AT 1180' WITH 10 SX GEL & 50 SX CMT. PLUG AT 450' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: KENNY SULLIVAN Witness Type: PARTIAL
Date/Time Plugging Completed: 10/31/2016 4:50 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

Perfs:

RAN TBG TO 4747' & PUMPED 25 SX CMT WITH 100# HULLS. PULLED TBG OUT OF HOLE. 1ST PLUG AT 1180' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 450' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT. CMT CIRCULATED.

Top	Bot	Thru	Comments
4742	4772		

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC ENERGY.

Plugged through: CSG

District: 01

Signed [Signature]

(TECHNICIAN)

RECEIVED
NOV - 2 2016
KCC DODGE CITY

NOV 21 2016
[Signature]

Form CP-2/3