

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-051-02320-00-00
Spot: NESWNW Sec/Twnshp/Rge: 26-11S-19W
1650 feet from N Section Line, 4290 feet from E Section Line
Lease Name: VINE A Well #: 4
County: ELLIS Total Vertical Depth: 3628 feet

Operator License No.: 5259
Op Name: MAI OIL OPERATIONS, INC.
Address: 8411 PRESTON RD STE 800
DALLAS, TX 75225

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3622		600 SX
SURF	8.625	145		100 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/31/2016 10:00 AM
Plug Co. License No.: 99977 Plug Co. Name: QUALITY OIL WELL CEMENTING
Proposal Rcvd. from: KENT WILLSON Company: MAI OIL OPERATIONS Phone: (785) 483-1683

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix 4% gel cement w/500 # hulls.
Open hole completion

Plugging Proposal Received By: PAT STAAB WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 10/31/2016 1:30 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Ran tubing to 3600' and pumped 180 sx cement w/250 # hulls. Pulled tubing to 1800' and pumped 170 sx cement w/250 # hulls to circulate cement to surface. Pulled all tubing, Hooked to 5 1/2" casing and pumped 35 sx cement to circulate 8 5/8" x 5 1/2" annulus. Topped off 5 1/2" casing with 5 sx cement.

GPS: 39.06915N -099.40426W

Perfs:

Received
KANSAS CORPORATION COMMISSION
NOV 18 2016
CONSERVATION DIVISION
WICHITA, KS

Remarks: QUALITY OILWELL CEMENTING TICKET # 3060

Plugged through: TBG

District: 04

Signed _____

Pat Bedore
(TECHNICIAN)

CM

NOV 04 2016

NOV 21 2016

Form CP-2/3

NO