

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-051-24974-00-00  
Spot: SENWNWSW Sec/Twnshp/Rge: 6-11S-20W  
2255 feet from S Section Line, 4749 feet from E Section Line  
Lease Name: WHISMAN Well #: 1  
County: ELLIS Total Vertical Depth: 3674 feet

Operator License No.: 5259  
Op Name: MAI OIL OPERATIONS, INC.  
Address: 8411 PRESTON RD STE 800  
DALLAS, TX 75225

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3672		150 SX
SURF	8.625	224		200 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/12/2016 9:30 AM  
Plug Co. License No.: 33771 Plug Co. Name: ULTIMATE WELL SERVICE, LLC  
Proposal Rcvd. from: KENT WILLSON Company: MAI OIL OPERATIONS Phone: (785) 483-1683

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix 4% gel cement w/1000 # hulls.  
PC at 1482' w/175 sx cement.  
Casing leaks

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 10/12/2016 2:30 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Ran in hole with tubing to 3500'. Quality rigged to tubing, mixed and pumped 150 sx cement w/300 # hulls mixed in. Pulled tubing to 2050' and pumped 140 sx cement w/200 # hulls mixed in to circulate cement to surface. Pulled tubing. Topped off 5 1/2' casing with 15 sx cement. Hole standing full. 8 5/8" surface casing full of cement.

GPS: 39.12320 -099.59055

Perfs:

Top	Bot	Thru	Comments
3656	3660		
3633	3641		

Remarks: QUALITY OIL WELL CEMENTING TICKET # 7845

Plugged through: TBG

District: 04

Signed



(TECHNICIAN)

CM

KCC WICHITA

OCT 31 2016

RECEIVED

NOV 21 2016

NO

Form CP-2/3

OCT 17 2016