

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-009-25384-00-00  
Spot: N2S2NE Sec/Twnshp/Rge: 30-17S-14W  
1570 feet from N Section Line, 1390 feet from E Section Line  
Lease Name: MANETH-MCCURRY UNIT Well #: 1  
County: BARTON Total Vertical Depth: 3388 feet

Operator License No.: 5259  
Op Name: MAI OIL OPERATIONS, INC.  
Address: 8411 PRESTON RD STE 800  
DALLAS, TX 75225

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3487	2400	150 SX
SURF	8.625	918		375 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/06/2016 8:00 AM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: ALLEN BANGERT Company: MAI OIL OPERATIONS Phone: (785) 483-2169

Proposed Plugging Method: Ordered 350 sx 60/40 pozmix 4% gel cement w/400 # hulls.

Plugging Proposal Received By: BRUCE RODIE Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 10/16/2016 12:00 AM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Sanded back to 3250' and topped with 5 sx cement. Cut casing at 2400' and pulled to 1400'. Tied to casing and pumped 125 sx cement w/200 # hulls. Pulled casing to 900' and pumped 50 sx cement w/100 # hulls. Pulled casing to 600' and pumped 50 sx cement w/100 # hulls. Pulled casing to 250' and pumped 50 sx cement. Circulated cement to surface. Pulled casing and hole stayed full.

GPS: 38.54606 -098.90903

Perfs:

Top	Bot	Thru	Comments
3430	3434		

Remarks: QUALITY OILWELL CEMENTING

Plugged through: CSG

District: 04

Signed Bruce Rodie  
(TECHNICIAN)

KCC WICHITA  
OCT 31 2016  
RECEIVED

NOV 21 2016  
RD

CM  
Form CP-2/3

OCT 17 2016