

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-163-21376-00-00
Spot: SWSWSE Sec/Twnshp/Rge: 16-7S-19W
330 feet from S Section Line, 2310 feet from E Section Line
Lease Name: R L MUIR Well #: 1
County: ROOKS Total Vertical Depth: 3533 feet

Operator License No.: 8061
Op Name: OIL PRODUCERS, INC. OF KANSAS
Address: 1710 WATERFRONT PKWY
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3533		350 SX
SURF	8.625	223		130 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/25/2016 12:30 PM
Plug Co. License No.: 34141 Plug Co. Name: MOHEGAN WELL SERVICE, LLC
Proposal Rcvd. from: JORDAN DISKIN Company: OIL PRODUCERS, INC. OF KANSAS Phone: (316) 681-0231

Proposed Plugging Method: Ordered 400 sx 60/40 pozmix 4% gel-cement w/600 # hulls.
Tubing anchor stuck in hole at 2950'.
1999- Squeezed 963' - 1155' w/100 sx cement.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 10/25/2016 12:30 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Perforated at 2000', 1500' and 750'. Ran tubing to 2931' and pumped 150 sx neat cement 60/40 pozmix 4% gel. Pulled tubing to 1512' and pumped 100 sx cement w/300 # hulls. Pulled tubing to 750' and pumped 100 sx cement w/300 # hulls to circulate cement to surface. Pulled all tubing and topped off 5 1/2" casing with 15 sx cement. Hooked to 8 5/8' x 5 1/2' annulus and pumped 15 sx cement. Shut in pressure 400 psi.

GPS: 39.43845N -099.44344W

Perfs:

Top	Bot	Thru	Comments
3436	3440		
3326	3330		
3304	3310		

Received
KANSAS CORPORATION COMMISSION
NOV 18 2016
CONSERVATION DIVISION
WICHITA, KS

Remarks: HURRICANE SERVICES INC. TICKET # 100698

Plugged through: TBG

District: 04

Signed _____

Pat Bedore
(TECHNICIAN)

CM

NOV 21 2016

no

Form CP-2/3

NOV 04 2016