


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

15-009-05562-8000
WELL PLUGGING RECORD



Locate well correctly on above Section Flat

Barton County. Sec. 31 Twp. 16 Rge. 11 (E) (W) (W)
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines SW SW NE
Lease Owner Bennett & Roberts Oil Operations
Lease Name Valenta Well No. 1
Office Address 205 Russell State Bank Bldg., Russell, Ks.
Character of Well (completed as Oil, Gas or Dry Hole) Dry hole
Date well completed 8/31 19 53
Application for plugging filed 9/8 19 53
Application for plugging approved 9/9 19 53
Plugging commenced 9/7 19 53
Plugging completed 9/10 19 53
Reason for abandonment of well or producing formation Dry hole.

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well C. D. Stough
Producing formation Depth to top Bottom Total Depth of Well 3383 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8"	360'	None
				5 1/2"	3091'	2475'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plugged back with crushed rock to 3000', dumped 5 sacks cement at 3000' with dump bailer, top of cement 2965'. Filled hole with mud to 300', set rock bridge, dumped 20 sacks cement. Top of cement, 230'. Filled hole with mud to 35', set rock bridge, dumped 10 sacks cement for cap.


(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Miller Casing Pulling Company
Address Great Bend, Ks.

STATE OF KANSAS, COUNTY OF RUSSELL, ss.
C. L. Roberts (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *C. L. Roberts*
Russell, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 14 day of September, 1953.
Clara Hummel
Notary Public.

My commission expires 6/17/54 23-8390-3 6-51-20M



Bennett & Roberts Drilling Co.
Valenta #1

Sec. 31 Twp. 16 Rge. 11W
SW SW NE

TD 3383
Comm: 6/15/53
Comp: 7/1/53

Tops:

Topeka Lime	2710(- 810)
Heebner Shale	2958(-1048)
Toronto Lime	2977(-1067)
Douglas Sand	3006(-1096)
Brown Lime	3059(-1159)
Lansing	3076(-1176)
Conglomerate	3339(-1439)
Arbuckle	3356(-1456)

Casing
8 5/8" Set @ 360'
5 1/2" Set @ 3091'

Cement
175 Sacks
100 Sacks

Formation:	Depth:
Surface Clay	25'
Shale & Shells	530
Red Bed	650
Shale & Shells	750
Anhydrite	780
Shale & Shells	1235
Salt & Shale	1410
Shale & Shells	1480
Lime & Shale	2500
Shale	2647
Lime & Shale	3155
Lime	3339
Conglomerate	3357
Arbuckle	3383

STATE OF KANSAS)
COUNTY OF RUSSELL)

I hereby certify that the above information is true and correct to the best of my knowledge.

Iris Lake

Subscribed and sworn to before me this 7th day of July, 1953.

Clara Hummel
Notary Public

My commission expires 6/17/54

PLUGGING
FILE SEC 31 T 16 R 11W
BOOK PAGE 127 LINE 30