

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

#4V 15-009-03158-0004
 API NUMBER NONE DRILLED in 1953

LEASE NAME ZORN

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

WELL NUMBER 6

4290 Ft. from S Section Line

3960 Ft. from E Section Line

SEC. 31 TWP. 16 RGE. 11 (E or W)

LEASE OPERATOR ROBINOWITZ OIL COMPANY

ADDRESS 7130 S. LEWIS, SUITE 910, TULSA, OK. 74136

COUNTY BARTON

PHONE#(918) 481-7130 OPERATORS LICENSE NO. 6883

Date Well Completed 10-29-53

Character of Well INPUT

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 7-12-88

by MARION SCHMIDT

RECEIVED
 STATE CORPORATION COMMISSION
 08-25-88
 AUG 25 1988
 (K000 District Agent's Name).

Plugging Commenced 7-18-88

Completed 7-25-88

Is ACO-1 filed? NO If not, is well log attached? NO

OLD WELL-DATA PREVIOUSLY FILLED

Producing Formation INPUT Depth to Top 2865 Bottom 2965 T.D. 3313

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
TOPEKA	OIL & WATER	2865	75	8 5/8	747	NONE
DOUGLAS	"	2955	65	5 1/2	3255	NONE
LANSING	"	3026-3234				
QUARTZITE	"	3244	TD			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
PUMPED 50 SX COMMON, FOLLOWED BY 350 SX THIFTYMIX W/ 3 SX FLOW SEAL DOWN 5 1/2".
WOG 2 1/2 HRS. PUMP 300 SX THIFTYMIX & 4 SX HILLS DOWN 5 1/2"- DID NOT CIRCULATE
WOG OVERNIGHT, CEMENT @ 213" IN 5 1/2" IN MORNING. PUMP 15 SX DOWN 5 1/2"
& 75 SX DOWN 8 5/8-5 1/2 ANNULUS. PRESSURE TO 300# WOG CUT OFF PIPE. CAP WELL
& RESTORE LOCATION.

Name of Plugging Contractor BJ-TITAN SERVICE License No. _____

Address GREAT BEND, KANSAS

STATE OF OKLAHOMA COUNTY OF TULSA, ss.

CHARLES E. SON (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Charles E. Son

(Address) SAME AS ABOVE

SUBSCRIBED AND SWORN TO before me this 22ND day of AUGUST, 19 88

Michael J. Wilson
 Notary Public

My Commission Expires: May 22, 1992