



15.075.30021.00.00

JOHN ANDERSON, Jr. Governor
WILLIAM L. MITCHELL, Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
MAY 14 1965
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Adminstrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Calhoun of Sunray DX Oil Co. has this date requested permission to plug the following described well:

Mr. Calhoun guarantees payment of the plugging fee.

Operator's full Name: Sunray DX Oil Co.

Complete Address: 300 Union Nat'l Bldg. Wichita, Kansas

Lease Name: C.E. Eagle Well No. # 1

Location: C SE NW Sec. 4 Twp. 23 Rge. 40(N)(W)

County Hamilton Total Depth 2640' Oil Well

Gas Well X Input Well SWD Well D & A X Lost Hole

Mr. Calhoun was instructed to plug the well as follows:

8 5/8"-382' Circulated w/cement. 4 1/2"-2639' Cemented.

Plug back to 2592'. Perforations 2569' to 2575'

Plug bottom w/20 Sax.cement top cement 2400'. Mud 2400' to 387'

Plug, 35 Sax.cement 387' to 280' Mud 280' to 45'

Plug, 15 Sax.cement, 45' to 0

Very truly yours,

Hugh Scott
Conservation Division Agent