



JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS
 JEWEL M. OGDEN, Director

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION
 AUG 9 1 1962
 CONSERVATION DIVISION
 Wichita, Kansas
 8-21-62

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

I have this date 8 - 13, 1962, authorized the following plugging operation:

Operator's full Name: Wakefield Earl F.

Complete Address: 515 Union Center Wichita Kan.

Lease Name: Moeckel Well No. # 1

Location: SE- SE- Sec. 13 Twp. 23 Rge. 10 (E)(W)**

County: Reno Total Depth: 3985

Oil Well Gas Well Input Well SWD Well

D & A Other well as hereafter indicated: _____

Operator was instructed to plug well as follows:

257' of 8 5/8" surface pipe circulated 225 sacks cement. Hole filled to 180' with heavy drilling mud 1/2 sack hulls 1st cementing plug & 20 sacks ~~1/2~~ cement. Hole filled to 35' with heavy drilling mud 1/2 sack hulls 2nd cementing plug & 10 sacks cement to bottom of cellar. Rat hole bridged 2 sacks cement.

Very truly yours,

Herman Justus

