

State of Kansas



15-055-00287-0008

JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

RECEIVED
 CORPORATION COMMISSION

OCT 8 1962

CONSERVATION DIVISION
 Wichita, Kansas

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agency)

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

I have this date 2 October, 1962, authorized

The following plugging operation:

Operator's full Name: National Cooperative Refinery Assoc.

Complete Address: 305 Rule Bldg., Wichita, Kansas

Lease Name: Damme Well No. # 3

Location: NE NW SW Sec. 21 Twp. 22 Rge. 33 (P) (W)

County Finney Total Depth: 4805'

Oil Well Gas Well Input Well SWD Well

D & A Other well as hereafter indicated:

Operator was instructed to plug well as follows:

8 5/8" 260' Cemented w/150 sax. 5 1/2" 4805' Cemented w/100 sax.

Plug back to 4712' Perf. 4702-4704'

Plug bottom w/sand and 4 sax. cement 4712' to 4600'

Heavy mud 4600' to 250' Plug and 35 sax. cement 250' to 150'

Heavy mud 150' to 40' Plug and 15 sax. cement 40' to surface.

Very truly yours,

Hugh [Signature]

