



JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION

JAN 3 1963

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

CONSERVATION DIVISION
 Wichita, Kansas

Dear Sir:

Mr. Dee Morton of Texaco Inc. has this

date requested permission to plug the following described well:

Mr. Dee Morton guarantees payment of the plugging fee.

Operator's full Name: Texaco Inc.

Complete Address: 614 Bitting Bldg. Wichita, Kansas

Lease Name: O.J.Walters"B" Well No. #.1

Location: C SW NW Sec. 22 Twp. 22 Rge. (E) (W) 33

County Finney Total Depth 4800' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Dee Morton was instructed to plug the well as follows:

8 5/8" 397' Circulated w/cement. 4 1/2" 4800' Cemented.

Plug back to 4760' Top Perforations 4715'

Sand 4760' to 4700' 3 sax.cement 4700' to 4660'

Mud 4660' to 375' Plug and 35 sax.cement 375' to 275'

Mud 275' to 50' Rock bridge 50' to 45'

15 sax.cement 45' to Surface.

Very truly yours,

[Signature]
 Conservation Division Agent