

State of Kansas



FORM - CP-2

JOHN ANDERSON, Jr. Governor  
 RICHARD C. BYRD Chairman  
 ALVIN F. GRAUERHOLZ Commissioner  
 HARRY G. WILES Commissioner  
 RAYMOND B. HARVEY Secretary  
 CHARLES C. McCARTER Gen. Counsel

## State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)  
 500 Insurance Bldg. 212 N. Market  
 WICHITA, KANSAS

VERBAL PERMIT FORM  
 (To Be Filed By Plugging Agent)

RECEIVED  
 STATE CORPORATION COMMISSION

SEP 10 1963

J. P. Roberts  
 Assistant Director  
 500 Insurance Building  
 212 North Market  
 Wichita 2, Kansas

CONSERVATION DIVISION  
 Wichita, Kansas

Dear Sir:

Mr. Schmidlapp of Lonita Oil Corporation Inc has this date requested permission to plug the following described well:

Mr. Schmidlapp guarantees payment of the plugging fee.

Operator's full Name: Lonita Oil Corporation Inc.

Complete Address: 704 Bitting Bldg. Wichita, Kansas

Lease Name: Damme Well No. B-2

Location: NW NE SW Sec. 28 Twp. 22S Rge. 33 (E) (W)

County Finney Total Depth 4822' Oil Well

Gas Well  Input Well  SWD Well  D & A  Lost Hole

Mr. Schmidlapp was instructed to plug the well as follows:

8 5/8"-375' Circulated w/cement.

Mud 4822' to 2700' Spotted 100 Sax.cement 2700' to 2200'

Mud 2200' to 375' Spotted 35 Sax.cement 375' to 275'

Mud 275' to 40' Plug, Hulls, 15 Sax.cement 40' to surface.

Very truly yours,

*F. Hugh Scott*  
 Conservation Division Agent