



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
JAN 6 1970
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Burris of Chief Drlg., Co. has this date requested permission to plug the following described well:

Mr. Burris guarantees payment of the plugging fee.

Operator's full Name: Chief Drilling Co. Inc.

Complete Address: Suite 905 Century Plaza, Wichita, Kansas

Lease Name: Brunfield Well No. 1

Location: 150' W of NW NE Sec. 30 Twp. 22 Rge. 24 XX (E) (W)

County: Hodgeman Total Depth 4680' Oil Well X

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Burris was instructed to plug the well as follows:

8 5/8" to 260' circulated w/ cement. Mud 4680' to 800'

Spot 80 sacks cement 800' to 500'. Mud 500' to 260'.

Spot 30 sacks cement 260' to 160'. Mud 160' to 45'.

Plug, Halls & 15 sacks cement 45' to 0'.

Very truly yours,

Conservation Division Agent