



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian  
WICHITA, KANSAS 67217

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 25 1973  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Norwood of Okmar has this

date requested permission to plug the following described well:

Mr. Norwood guarantees payment of the plugging fee.

Operator's full Name: Okmar Oil Co.

Complete Address: 1130 Vickers KSB&T Bldg., Wichita, Kansas

Lease Name: Cavanaugh Well No. 1

Location: C NW SE Sec. 18 Twp. 22 Rge. 24 ~~(E)~~ (W)

County: Hodgeman Total Depth 4660' Oil Well

Gas Well  Input Well  SWD Well  D & A  Lost Hole

Mr. Norwood was instructed to plug the well as follows:

8 5/8" to 249' circulated w/ cement. Mud 4660' to 800'

Spot 80 sacks cement 800' to 500' Mud 500' to 240'

Spot 30 sacks cement 240' to 140' Mud 140' to 45'

Plug, Hulls & 15 sacks cement 45' to 0'.

Very truly yours,

Conservation Division Agent