



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
FEB 8 1972
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Steincamp of Thunderbird has this

date requested permission to plug the following described well:

Mr. Steincamp guarantees payment of the plugging fee.

Operator's full Name: Thunderbird & Petroleum Resources

Complete Address: Box 18407, Wichita, Kansas

Lease Name: Malone Well No. 1

Location: NW SE Sec. 9 Twp. 22 Rge. 21 (W)

County: Hodgeman Total Depth 4368' Oil Well X

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Steincamp was instructed to plug the well as follows:

8 5/8" to 368' circulated w/ cement. Mud 4368' to 850'

Spot 80 sacks cement 850' to 550' Mud 550' to 360'

Spot 30 sacks cement 360' to 260' Mud 260' to 45'

Plug, Halls & 15 sacks cement 45' to 0'.

Very truly yours,

Conservation Division Agent