



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market

WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
JUN 14 1972
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Weber of Thunderbird has this

date requested permission to plug the following described well:

Mr. Weber guarantees payment of the plugging fee.

Operator's full Name: Thunderbird Drilling Co.

Complete Address: Box 18407, Wichita, Kansas

Lease Name: Hastings Well No. 1

Location: NE SW Sec. 9 Twp. 22 Rge. 21 ~~(E)~~ (W)

County: Hodgeman Total Depth 4365' Oil Well

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Weber was instructed to plug the well as follows:

8 5/8" to 364' circulated w/ cement. 5 1/2" to 4358' circulated w/ cement.

Open hole 4358' to 43652' Plug bottom w/ 20 sacks cement.

Top of cement 4100' Mud 4100' to 700'

Spot 15 sacks cement 700' to 600' Mud 600' to 40'

Plug & 5 sacks cement 40' to 0'.

Very truly yours,

Edgar J. Eves
Conservation Division Agent