



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

RECEIVED  
STATE CORPORATION COMMISSION  
FEB 10 1970  
CONSERVATION DIVISION  
Wichita, Kansas

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Burton of Pickrell has this date requested permission to plug the following described well:

Mr. Burton guarantees payment of the plugging fee.

Operator's full Name: Pickrell Drilling Co.

Complete Address: 705 4th Nat'l Bank Bldg., Wichita, Kansas

Lease Name: Dovel "A" Well No. 1

Location: C NE SW Sec. 5 Twp. 22 Rge. 21 ~~(E)~~ (W)

County: Hodgeman Total Depth 4384 Oil Well X

Gas Well      Input Well      SWD Well      D & A X Lost Hole     

Mr. Burton was instructed to plug the well as follows:

8 5/8" to 281' circulated w/ cement. Mud 4384' to 850'

Spot 80 sacks cement 850' to 550' Mud 550' to 280'

Spot 30 sacks cement 280' to 180' Mud 180' to 45'

Plug, HuKls & 15 sacks cement 45' to 0'.

Very truly yours,

Conservation Division Agent