

1 070212

160 R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 083-21,258-0000
SW NE SW, SEC. 26, T 22 S, R 24 W/E
1650 feet from S section line
3630 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6177
Operator: Foxfire Exploration, Inc.
Name & Address 1022 Union Center
Wichita, KS 67202

Lease Name Ford Well # 1
County Hodgeman 150.48
Well Total Depth 4630 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 453

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Foxfire Drilling Co., Inc. License Number 8430
Address Wakeeney, KS 67672

Company to plug at: Hour: 6:30 a.m. Day: 27 Month: 8 Year: 19 86

Plugging proposal received from Gary Fisher

(company name) Foxfire Drilling (phone) 913-743-5337

were: to fill hole with heavy mud and spot cement through drill pipe Elevation 2355' GL

- 1st plug at base Anhydrite at approximately 1600' with 50 sx of cement
- 2nd plug at 1/2 Anhydrite plus 100' (approximately 900') with 80 sx of cement
- 3rd plug at Base Surface plus 30' with 50 sx of cement
- 4th plug at 40' with 10 sx cement
- 5th plug to circulate rat hole with 15 sx cement

Plugging Proposal Received by Dan Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part X None _____

Operations Completed: Hour: 9:30 a.m. Day: 27 Month: 8 Year: 19 86

ACTUAL PLUGGING REPORT 1st plug at 1650' with 50 sx cement
2nd plug at 950' with 80 sx cement
3rd plug at 480' with 50 sx cement
4th plug at 40-0' with 10 sx cement
5th plug to circulate rathole with 15 sx cement

Used 60/40 Pozmix 6% gel by Allied.

Remarks: _____
(If additional description is necessary, use BACK of this form.)

INVOICED Observe this plugging.

Signed Dan Goodrow
(TECHNICIAN)

DATE 9-2-86

INV. NO. 14840 SEP 29 1986 8-29-86