

1050298

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 083-21,075-0000

C NW SE SE SEC. 23 T 22 S, R. 24 <sup>(W)</sup> <sub>(E)</sub>  
N SE Corner of  
990 feet from ~~XXX~~ section line  
W SE Corner of  
990 feet from ~~XXX~~ section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5004

Lease Name Springer Well # 1

Operator: Vincent Oil Corporation

County Hodgeman

Name & Address 125 North Market, Suite 1110

Well Total Depth 4689 152.39 feet

Wichita, KS 67202

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 512 500

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 9:00 am Day: 30 Month: July Year: 1984

Plugging proposal received from Neal Petticord

(company name) Kelso (phone) 316-938-2457

were: 4 1/2" set at 4689' PBTD 4462' Perfs 4446-4654'

1st plug sand back to 4390' and dump 4 sx cement on top of sand through bailer

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, release 8 5/8" rubber plug and pump an additional 150 sx cement.

Plugging Proposal Received by Richard W. Lacey  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 10:45 am Day: 30 Month: July Year: 19 84

ACTUAL PLUGGING REPORT 4 1/2" set at 4689' PBTD 4462' Perfs 4446-4654' 8-1-84

1st plug pumped 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, released 8 5/8" rubber plug and pumped an additional 150 sx cement.

RECEIVED  
STATE CORPORATION COMMISSION

Maximum pressure 900 psi and shut in pressure 400 psi

AUG 01 1984

CONSERVATION DIVISION  
Wichita, Kansas

Remarks: They recovered 2700' 4 1/2" casing. Used 60/40 Pozmix 2% gel 3% cc by Allied.  
(If additional description is necessary, use BACK of this form.)

INVOICED

(If additional description is necessary, use BACK of this form.) observe this plugging.

DATE 8-4-84

Signed Richard W. Lacey  
(TECHNICIAN)

INV NO. 2861