

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Kingman SEC. 28 TWP. 20 RGE. 9 NE/W
Location as in quarters or footage from lines:
C-NE-NW-SE

Lease Owner Harris Exploration Company
Lease Name Werner Well No. 1
Office Address 1341 W. Mockingbird Ln. #1200E Dallas, Texas 75247
Character of Well (Completed as Oil, Gas or Dry Hole): DH
Date Well Completed Dry Hole
Application for plugging filed Called KCC 1/15/82
Plugging commenced 1/15/82
Plugging completed 1/15/82
Reason for abandonment of well or producing formation Dry

Locate Well
correctly on above
Section Platt.

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Maurice Leslie

Producing formation None Depth to top _____ bottom _____ T.D. 4,686'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
Kinderhook Shale	Water	4484	4485	8 5/8"	335'	0
Viola	Water	4583	4589			
Simpson Sand	Water	4646	4649			

Describe in detail the manner in which the well was plugged, indicating where the mud
fluid was placed and the method or methods used in introducing it into the hold. If cement
or other plugs were used, state the character of same and depth placed, from _____ feet
to _____ feet for each plug set.

Well drilled to 4686' Mud characters during period 9.3 Vis 31. Pumped 60 sks class
"A" cement to 720'; 40 sks @ 325'; 10 sks @ 40' and 10 sks @ surface.

2-1-82

RECEIVED
STATE CORPORATION COMMISSION

FEB - 1 1982

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Gabbert-Jones, Inc. CONSERVATION DIVISION
Wichita, Kansas

STATE OF Texas COUNTY OF Dallas, ss.
Stephen M. Brazeal (employee of owner) or (owner or operator) of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.

(Signature) Stephen M. Brazeal
1341 W. Mockingbird, Dallas, Tx.
(Address)

SUBSCRIBED AND SWORN TO before me this 28th day of January, 1982

Barbara Barber
Notary Public.

My Commission expires: 12/11/85

GABBERT-JONES, INC.
 WICHITA, KANSAS
 DRILLERS' WELL LOG

Werner #1
 NE-NW-SE Sec 28-30S-9W
 Kingman County Kansas

Commenced: 1-3-82

Completed: 1-15-82

OPERATOR: HARRIS EXPLORATION CO.

Depth		Formation	Remarks
From	To		
0	352	Clay-Redbed	
352	665	Shale-Clay	
665	1720	Shale	Ran 6 jts of 23# 8 5/8"
1720	2025	Shale-Shells	csg set @ 335' Cemented
2025	2570	Shale-Lime	w/300 sks Common 3% CC
2570	2787	Shale	2% Gel PD @ 11:00 p.m. 1-3-82
2787	3285	Lime-Shale	
3285	3517	Shale	
3517	4686	Lime-Shale	
	4686 - TD		DRY & ABANDONED

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

I, the undersigned, being duly sworn on oath, state that the above
 Drillers' Well Log is true and correct to the best of my knowledge and belief and
 according to the records of this office.


GABBERT-JONES, INC.

James S. Sutton II
 JAMES S. SUTTON II

Subscribed and sworn to before me this 20th day of January, 1982.

Elizabeth J. Edwards
 ELIZABETH J. EDWARDS-NOTARY PUBLIC

My Commission expires February 6, 1983.



RECEIVED
 STATE CORPORATION COMMISSION

FEB - 1 1982

CONSERVATION DIVISION
 Wichita, Kansas