

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
July 2014
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 35269
Name: CK Oil & Gas, LLC
Address 1: 906 E Trapp St
Address 2: _____
City: Herington State: KS Zip: 67449 + 8901
Contact Person: Charles Kremeier
Phone: (405) 202-3481
Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENHR Permit #: _____ Gas Storage Permit #: _____
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (if needed attach another sheet)
Arbuckle Depth to Top: 2959 Bottom: _____ T.D. 2968
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API No. 15 - 035-01148-00-00
Spot Description: _____
NW NW SW Sec. 5 Twp. 30 S. R. 4 East West
2,310 Feet from North / South Line of Section
4,950 Feet from East / West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Cowley
Lease Name: Cooley Well #: 1
Date Well Completed: 10/25/1963
The plugging proposal was approved on: 11/09/2016 (Date)
by: Jeff Klock (KCC District Agent's Name)
Plugging Commenced: 11/14/2016
Plugging Completed: 11/15/2016

Show depth and thickness of all water, oil and gas formations.

| Oil, Gas or Water Records | | Casing Record (Surface, Conductor & Production) | | | |
|---------------------------|---------|---|-------|----------------------|------------|
| Formation | Content | Casing | Size | Setting Depth | Pulled Out |
| | | | 8.625 | 112 | 0 |
| | | | 5.5 | 2959 2960 | 540 |
| | | | | | |
| | | | | | |

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Set CIBP at 2915', spotted 2 sacks cement with bailer on plug, came up to 540', shot casing, pulled casing, ran tubing to 317', pumped cement plug to surface.

Received
KANSAS CORPORATION COMMISSION
NOV 17 2016
CONSERVATION DIVISION
WICHITA, KS

Plugging Contractor License #: 30483 Name: Kremeier, Les (deceased) Kremeier Prod
Address 1: 3183 US Hwy 56 Address 2: _____
City: Herington State: KS Zip: 67449 + _____
Phone: (785) 258-2321
Name of Party Responsible for Plugging Fees: CK Oil & Gas, LLC
State of Kansas County, Dickinson, ss.
Charles Kremeier Employee of Operator or Operator on above-described well,
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: Charles Kremeier

810 E 7TH
 PO Box 92
 EUREKA, KS 67045
 (620) 583-5561



Cement or Acid Field Report
 Ticket No. **3015**
 Foreman Steve Mead
 Camp Eureka KS

| Date | Cust. ID # | Lease & Well Number | Section | Township | Range | County | State | |
|------------------------------------|------------|---------------------|----------------|----------|--------|---------|--------|--------|
| 11-14-16 | 1207 | Copley #1 | | | | Butter | KS | |
| Customer C KOil + Gas LLC | | | Safety Meeting | | Unit # | Driver | Unit # | Driver |
| Mailing Address 906 E Trapp St. | | | | | 104 | Alan M | | |
| City Herington | | | | | 112 | Kevin M | | |
| State KS | | | | | | | | |
| Zip Code 67449 | | | | | | | | |

Job Type PIA Hole Depth _____ Slurry Vol. _____ Tubing 2 7/8 317'
 Casing Depth _____ Hole Size _____ Slurry Wt. _____ Drill Pipe _____
 Casing Size & Wt. 5 1/2 Cement Left in Casing _____ Water Gal/SK _____ Other _____
 Displacement _____ Displacement PSI _____ Bump Plug to _____ BPM _____

Remarks: Safety Meeting: Rise up to 2 7/8 Tubing. Break Circulation w/ 10 bbls Freshwater Mix 275 SKs 60/40 Poz mix Cement w/ 4% Gel. 317' To Surface Pull out Tubing. Top well off. Job Complete. Rig down

Thank you

| Code | Qty or Units | Description of Product or Services | Unit Price | Total |
|---|-------------------|------------------------------------|-----------------|---------|
| C105 | 1 | Pump Charge | 750.00 | 750.00 |
| C107 | 30 | Mileage | 3.95 | 118.50 |
| C203 | 175 | 60/40 Poz mix Cement | 12.75 | 2231.25 |
| C306 | 600 ^{lb} | 4% Gel | .20 | 120.00 |
| C108A | 7.53 Ton | Ton Mileage Bulk Trucks | m/c | 345.00 |
| | | | Sub Total | 3564.75 |
| | | | 6.75% Sales Tax | 240.62 |
| Authorization <u>Called by Chris Kremsier Title Co. Rep</u> | | | Total | 3805.37 |

Received
 KANSAS CORPORATION COMMISSION
 NOV 17 2016
 CONSERVATION DIVISION
 WICHITA, KS

I agree to the payment terms and conditions of services provided on the back of this job ticket. Any amendments to payment terms must be in writing on the front of this job ticket or in the Customer's records at ELITE's office.