

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING RECORD**  
K.A.R. 82-3-117

Form CP-4  
July 2014  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

OPERATOR: License #: 35269  
Name: CK Oil & Gas, LLC  
Address 1: 906 E Trapp St  
Address 2: \_\_\_\_\_  
City: Herington State: KS Zip: 67449 + 8901  
Contact Person: Charles Kremeier  
Phone: (405) 202-3481  
Type of Well: (Check one)  Oil Well  Gas Well  OG  D&A  Cathodic  
 Water Supply Well  Other: \_\_\_\_\_  SWD Permit #: \_\_\_\_\_  
 ENHR Permit #: \_\_\_\_\_  Gas Storage Permit #: \_\_\_\_\_  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (if needed attach another sheet)  
Arbuckle Depth to Top: 2983 Bottom: 2986 T.D. 3050  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API No. 15 - 015-23772-00-00  
Spot Description: \_\_\_\_\_  
N2 S2 SE NW Sec. 32 Twp. 29 S. R. 4  East  West  
3,135 Feet from  North /  South Line of Section  
1,980 Feet from  East /  West Line of Section  
Footages Calculated from Nearest Outside Section Corner:  
 NE  NW  SE  SW  
County: Butler  
Lease Name: Rock Well #: 1-32  
Date Well Completed: 5-20-08  
The plugging proposal was approved on: 11/09/2016 (Date)  
by: Jeff Klock (KCC District Agent's Name)  
Plugging Commenced: 11/09/2016  
Plugging Completed: 11/14/2016

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
			8.625	240	0
			5.5	3021	1450

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Set CIBP at 2930', spotted 2 sacks cement with bailer on plug, came up to 1450', shot casing, pulled casing, ran 10 joints tubing in, pumped cement plug to surface.

Received  
KANSAS CORPORATION COMMISSION  
**NOV 17 2016**  
CONSERVATION DIVISION  
WICHITA, KS

Plugging Contractor License #: 30483 Name: Kremeier, Les (deceased) Kremeier Prod  
Address 1: 3183 US Hwy 56 Address 2: \_\_\_\_\_  
City: Herington State: KS Zip: 67449 + \_\_\_\_\_  
Phone: (785) 258-2321  
Name of Party Responsible for Plugging Fees: CK Oil & Gas, LLC  
State of Kansas County, Dickinson, ss.  
Charles Kremeier  Employee of Operator or  Operator on above-described well,  
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: Charles Kremeier

810 E 7<sup>TH</sup>  
 PO Box 92  
 EUREKA, KS 67045  
 (620) 583-5561



**Cement or Acid Field Report**  
 Ticket No. **3014**  
 Foreman Steve Mead  
 Camp Eureka

Date	Cust. ID #	Lease & Well Number	Section	Township	Range	County	State
11-11-16	1207	Rock # 1-32				Butler	Ks
Customer C K Oil + Gas LLC			Safety Meeting	Unit #	Driver	Unit #	Driver
Mailing Address 906 E Trapp St				104	Blair M		
City Herington				112	Steve M		
State KS		Zip Code 67449					

Job Type PJA Hole Depth \_\_\_\_\_ Slurry Vol. \_\_\_\_\_ Tubing 2 3/8 315'  
 Casing Depth \_\_\_\_\_ Hole Size \_\_\_\_\_ Slurry Wt. \_\_\_\_\_ Drill Pipe \_\_\_\_\_  
 Casing Size & Wt. 5 1/2 Cement Left in Casing \_\_\_\_\_ Water Gal/SK \_\_\_\_\_ Other \_\_\_\_\_  
 Displacement \_\_\_\_\_ Displacement PSI \_\_\_\_\_ Bump Plug to \_\_\_\_\_ BPM \_\_\_\_\_

Remarks: Safety Meeting. Rig up to 2 3/8 Tubing Break circulation w/ 3 bbls Fresh Water Mix 115 SKs 60/40 Perm Cement w/ 4% Gel 315' to surface. Pull out Tubing Top well off. Job Complete Rig down

*Thank you*

Code	Qty or Units	Description of Product or Services	Unit Price	Total
C1052	1	Pump Charge	500.00	500.00
		Mileage <u>N/C</u>	-	-
C203	115 SKs	60/40 Perm Cement	12.75	1466.25
C206	395 "	Gel 4%	20	79.00
C108A	595 Ton	Ton Mileage Bulk Truck	<u>N/C</u>	345.00
Received KANSAS CORPORATION COMMISSION				
NOV 17 2016				
CONSERVATION DIVISION WICHITA, KS				
			Sub Total	2390.25
			Sales Tax <u>6.75%</u>	161.34

Authorization Called by Chris Krempner Title Co. Rep. Total 2551.59

I agree to the payment terms and conditions of services provided on the back of this job ticket. Any amendments to payment terms must be in writing on the front of this job ticket or in the Customer's records at ELITE's office.