

15.083-20430-0000

WELL PLUGGING RECORD

Give All Information Completely  
 Make Required Affidavit

COUNTY Hodgeman SEC. 26 TWP. 22 RGE. 24 E/W  
 Location as in quarters or footage from lines:  
C/NE/SW


Lease Owner Petroleum, Inc.  
 Lease Name Ford "G" Well No. #1  
 Office Address Box 1447 - Great Bend, Kansas 67530  
 Character of Well (Completed as Oil, Gas or Dry Hole): Oil  
 Date Well Completed \_\_\_\_\_  
 Application for plugging filed \_\_\_\_\_  
 Plugging commenced July 1, 1983  
 Plugging completed July 14, 1983  
 Reason for abandonment of well or producing formation  
Depleted

Locate Well  
 correctly on above  
 Section Platt.

Was permission obtained from the Conservation Division or it's  
 Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Richard Lacey

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom T.D. 4631'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8 5/8"	398'	NONE
				5 1/2"	4630'	2492.53'

Describe in detail the manner in which the well was plugged, indicating where the mud  
 fluid was placed and the method or methods used in introducing it into the hold. If cement  
 or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet  
 to \_\_\_\_\_ feet for each plug set.

Dumped sand to 4550' and five (5) sacks cement.  
Shot casing at 4000'. Casing parted.  
Ran fishing tool and shot casing at 3000', 2700' and 2500'.  
Pulled seventy-nine (79) joints 5 1/2" casing.  
Run squeezed well with three (3) sacks hulls, fifteen (15) sacks gel,  
seventy (70) sacks cement, ten (10) sacks gel, one (1) sack hulls, released  
plug and pumped one hundred fifty (150) sacks 50/50 pozmix cement with 4%  
added gel and 3% calcium chloride. Maximum pressure was 500 psi and  
shut in at 200 psi.

8-2-83


(If additional description is necessary, use BACK of this sheet)  
 Name of Plugging Contractor Rockhold Engineering, Inc. RECEIVED  
 STATE CORPORATION COMMISSION

AUG 02 1983

STATE OF KANSAS COUNTY OF BARTON, ss.  
James W. Rockhold (employee of owner) or (owner or operator) of the  
 above-described well, being first duly sworn on oath, says: That I have knowledge of the  
 facts, statements, and matters herein contained and the log of the above-described well as  
 filed and that the same are true and correct. So help me God.

(Signature) James W. Rockhold  
 JAMES W. ROCKHOLD - Box 698 - Great Bend, Ks.  
 (Address) 67530

SUBSCRIBED AND SWORN TO before me this 15th day of August, 1983



Margaret Prosser  
 Notary Public.

My Commission expires: \_\_\_\_\_

DRILLERS' LOG

PETROLEUM, INC.  
 No. 1 Ford 'G'  
 C NE SW, Sec. 26-22S-24W  
 Hodgeman County, Kansas

Elev: 2372 D.F.

Commenced: 8-1-75  
 Completed: 8-9-75

Surface Casing: 390' of  
 8-5/8" cemented w/275sx  
 common cement, 2% Gel,  
 3% cc. 8-1-75

FORMATIONDEPTH

Surface Hole	0 - 398
Shale	398 - 975
Blaine Anhydrite	975 - 988
Sand & Shale	988 - 1450
Shale & Red Bed	1450 - 1594
Anhydrite	1594 - 1628
Shale	1628 - 2505
Shale & Lime	2505 - 2670
Lime & Shale	2670 - 3825
Lime	3825 - 4210
Lime & Shale	4210 - 4375
Lime	4375 - 4620
Lime & Conglomerate	4620 - 4625
Lime	4625 - 4630 RTD

I do hereby certify that the foregoing statements are true and correct to the best of my knowledge and belief.

D N B DRILLING, INC.

*James L. Donelson*  
 JAMES L. DONELSON

STATE OF KANSAS: ss:

Subscribed and sworn to before me, this 14th day of August, 1975

My Commission Expires:  
 August 25, 1976

*Ella Priess*  
 Ella Priess, Notary Public

RECEIVED  
 STATE CORPORATION COMMISSION

MAR 4 1983

CONSERVATION DIVISION  
 Wichita, Kansas

*Ella Priess*  
 STATE NOTARY PUBLIC  
 Sedgwick County, Kansas  
 My Com. Expires Aug. 25, 1976