

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

WELL PLUGGING RECORD

API NUMBER 15-083-20,416-0000

LEASE NAME Ford

WELL NUMBER 1

SPOT LOCATION NE SE

SEC. 26 TWP. 22 RGE. 24 (E)OR(W)

COUNTY Hodgeman

DATE WELL COMPLETED 3/4/75

PLUGGING COMMENCED 9/21/83

PLUGGING COMPLETED 9/24/83

TYPE OR PRINT  
PLEASE FILL OUT COMPLETELY  
AND MAKE REQUIRED AFFIDAVIT.

LEASE OPERATOR The Dane G. Hansen Trust

ADDRESS Logan, Kansas 67646

PHONE # (913) 689-4816 OPERATORS LICENSE NO. 5285

CHARACTER OF WELL Oil  
(OIL, GAS, D&A, SWD, INPUT, WATER SUPPLY WELL)

DID YOU NOTIFY THE KCC/KDHE JOINT DISTRICT OFFICE PRIOR TO PLUGGING THIS WELL? Yes

WHICH KCC/KDHE JOINT OFFICE DID YOU NOTIFY? Dodge City

IS ACO-1 FILED? Yes IF NOT, IS WELL LOG ATTACHED? \_\_\_\_\_

PRODUCING FORMATION Mississippi DEPTH TO TOP 4624 BOTTOM 4633 T.D. 4633

SHOW DEPTH AND THICKNESS OF ALL WATER, OIL AND GAS FORMATIONS.

OIL, GAS OR WATER RECORDS \_\_\_\_\_ CASING RECORD \_\_\_\_\_

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Mississippi	Oil went to water	4624	33	8 5/8	412'	None
				5 1/2	4622.10	990'

DESCRIBE IN DETAIL THE MANNER IN WHICH THE WELL WAS PLUGGED, INDICATING WHERE THE MUD FLUID WAS PLACED AND THE METHOD OR METHODS USED IN INTRODUCING IT INTO THE HOLE. IF CEMENT OR OTHER PLUGS WERE USED STATE, THE CHARACTER OF SAME AND DEPTH PLACED, FROM FEET TO FEET EACH SET. Dumped 130 gal. sand in well while flushing with salt water and loaded hole. Ran jars to tag T.D. Hit bridge at 1020'. Spotted 2 sx. cement on bridge. Stretched casing. Shot off at 990'. Pumped 5 sx gel and 125 sx 60/40 poz. with 2% gel and 3% cc with max. press. 500# and shut in at 100#.

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

NAME OF PLUGGING CONTRACTOR Allied Cementing Co., Inc. LICENSE No. \_\_\_\_\_  
ADDRESS P. O. Box 31, Russell, Kansas 67665

STATE OF KANSAS COUNTY OF PHILLIPS, ss.

Dane G. Bales, Manager (EMPLOYEE OF OPERATOR) OR  
(OPERATOR) OF ABOVE-DESCRIBED WELL, BEING FIRST DULY SWORN ON OATH, SAYS: THAT  
I HAVE KNOWLEDGE OF THE FACTS, STATEMENTS, AND MATTERS HEREIN CONTAINED AND  
THE LOG OF THE ABOVE-DESCRIBED WELL AS FILED THAT THE SAME ARE TRUE AND  
CORRECT, SO HELP ME GOD.

(SIGNATURE) Dane G. Bales  
Dane G. Bales  
(ADDRESS) Logan, Kansas 67646



SUBSCRIBED AND SWORN TO BEFORE ME THIS 24 DAY OF October, 19 83

Betty Jane Bittel  
NOTARY PUBLIC

MY COMMISSION EXPIRES: July 17, 1984.

RECEIVED  
STATE CORPORATION COMMISSION  
OCT 27 1983  
FORM CP-4  
REVISED 06-83  
CONSERVATION DIVISION  
Wichita, Kansas