


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail & Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

WELL PLUGGING RECORD

Hodgman County, Sec. 30 Twp. 22 Rge. 24 (E) (W)

Location as "NE/CNW/SW" or footage from lines C/NE NW
Lease Owner Franco Central Oil Company
Lease Name Cambell Well No. 1
Office Address Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced 8-24-60 19____
Plugging completed 8-30-60 19____
Reason for abandonment of well or producing formation Depleted



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well Frank Broadfoot.
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4717' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	158'	None
				5-1/2"	4747'	3623'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Checked hole to 4700' and found it clear.
Ran 100 gal. of sand to 4615' and dumped
5 sacks of cement with dump bailer. Pulled
5 1/2" casing. Checked fluid to 290', set 10'
rock bridge to 280' and ran 20 sacks of cement.
Mudded hole to 40', set 10' rock bridge to 30'
and ran 10 sacks of cement to base of cellar.

PLUGGING COMPLETE.

RECEIVED
STATE CORPORATION COMMISSION
SEP 8 1960
CONSERVATION DIVISION
Wichita, Kansas

9-8-60

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor KNIGHT CASING PULLING CO.
Address CHASE, KANSAS

STATE OF KANSAS, COUNTY OF RICE, ss.
Noel J. Knight (employee of owner) or (owner/operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel J. Knight
Chase, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 31st day of August, 19 60

My commission expires May 20, 1964 Milton J. Volin Notary Public.

15.093.00065-0000
30-22-24W

R
DRILLERS LOG

No. 1 Campbell

CASING RECORD: COMPANY: Franco Central Oil Co. DESCRIPTION: C NE/4 NW 4
 8 5/8" @ 1560 CONTRACTOR: Red Tiger Drilling Co. 70-228-24W
 w/110 sx cement? COMMENCED: May 11, 1960 HODGEMAN COUNTY
 KANSAS
 8 1/2" @ 4747? ELEVATION: 2470 BP
 w/100 sx cement? COMPLETED: May 25, 1960 2473 BS
 TOTAL DEPTH: 4752'

FORMATION	FROM	TO	REMARKS
Surface Soil Clay	0	70	
Shale Shells	70	136	
Shale & Shells	136	390	
Sand & Shale	390	530	
Shale & Shells	530	1020	
Lime	1020	1085	
Shale & Shells	1085	1510	
Shale Shells	1510	1580	
Lime (Anhydrite)	1580	1875	
Shale Shells	1875	1760	
Shale & Shells	1760	2020	
Shale & Lime	2020	2180	
Shale & Shells	2180	2330	
Lime & Shale	2330	2445	
Lime Shale	2445	2585	
Lime	2585	2675	
Lime & Shale	2675	3092	
Shale & Lime	3092	3150	
Shale Lime	3150	3230	
Shale & Lime	3230	3470	
Shale Lime	3470	3585	
Shale & Lime	3585	3728	
Lime	3728	3755	
Lime Shale	3755	3835	
Lime & Shale	3835	4010	
Lime	4010	4615	
Lime & Chert	4615	4635	
Chert	4635	4645	
Mississippi	4645	4752	

RECEIVED
 TITLE CORPORATION COMMISSION
 SEP 15 1960
 CONSERVATION DIVISION
 Topeka, Kansas

I certify that this is a true and correct copy of the above log to the best of my knowledge.

RED TIGER DRILLING COMPANY

George A. Angle
George A. Angle

Subscribed and sworn to before me this 27th day of May, 1960.

Madame Heady
Notary Public

