

STATE OF KANSAS
STATE CORPORATION COMMISSION


Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Hodgeman County, Sec. 30 Twp. 22 Rge. 24W (E) (W)

Location as "NE/CNW/SW" or footage from lines 150' W of NW NE
Lease Owner Chief Drilling Co., Inc.
Lease Name Brumfield Well No. #1
Office Address Suite 905 Century Plaza, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry hole
Date well completed January 4, 1970 19
Application for plugging filed January 4, 1970 19
Application for plugging approved January 4, 1970 19
Plugging commenced January 4, 1970 19
Plugging completed January 4, 1970 19
Reason for abandonment of well or producing formation Dry hole



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Edgar J. Eves
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4680' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	260'	8 5/8"		

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged through drill pipe @ 800' w/80 sacks cement
Plugged through drill pipe @ 260' w/30 sacks cement
Plugged through drill pipe @ 40' w/15 sacks cement

1-6-70
RECEIVED
STATE CORPORATION COMMISSION
JAN 6 1970
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Chief Drilling Co., Inc.
Address Suite 905 Century Plaza, Wichita, Kansas 67202

STATE OF KANSAS, COUNTY OF SEDGWICK, ss:
Jim Robinson (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Jim Robinson
Suite 905 Century Plaza, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 5th day of January, 19 70

My commission expires May 9, 1971
Betty Brandt Notary Public.

15-093-20111-0000

WELL LOG

Chief Drilling Co., Inc.
905 Century Plaza
Wichita, Kansas 67202

#1 BRUMFIELD
150' W NW NE Sec. 30-22-24W
Hodgeman County

Contractor: Company Tools

Commenced: 12/22/69
Completed: 1/4/70

Casing Record: Set 260' of 8 5/8" w/165
sacks cement.

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>ELEVATION</u>
Surface clay	0	50	2484 Gr.
Shale & sand streaks	50	260	2486 D.F.
Shale	260	406	2489 K.B.
Sand, shale & red bed	565	1058	
Anhydrite	1058	1074	
Shale & red bed	1074	1110	
Shale, shells, sand strks.	1110	1670	
Anhydrite	1670	1702	
Shale	1702	1725	
Shale & shell	1725	2360	
Shale & lime	2360	4345	
Sime	4345	4650	
Cherty lime & shale	4650	4680	
RTD	4680		

<u>FORMATION TOPS</u>	
Anhydrite	1670 + 819
	1702 + 787
Heebner	3944 -1455
Toronto	3964 -1475
Lansing	3998 -1509
Base K.C.	4412 -1923
Marmaton	4424 -1935
Pawnee Shale	
Marker	4507 -2018
Ft. Scott	4549 -2060
Mississippian	4649 -2160
T.D.	4680 -2191

STATE OF KANSAS, COUNTY OF SEDGWICK) ss:

I hereby certify that the above is a true and correct copy of the Driller's Log of the well drilled 150' W of the NW NE of Sec: 30-22-24W, Hodgeman County, Kansas, to the best of my knowledge and belief.

CHIEF DRILLING CO., INC.

Jim Robinson
Jim Robinson, Office Mgr.

Subscribed and sworn to before me this 8th day of January, 1970.

Betty Brandt
Betty Brandt, Notary Public

My Commission Expires:

May 9, 1971

RECEIVED
STATE CORPORATION COMMISSION
JAN 9 1970
CONSERVATION DIVISION
Wichita, Kansas