


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above Section Plat

HODGEMAN County. Sec. 23 Twp. 22S Rge. 24 (X) (W)
Location as "NE/CNW/SW" or footage from lines APP. C SW NW
Lease Owner PETROLEUM, INC.,
Lease Name SPRINGER Well No. 4
Office Address R.R. #2, GREAT BEND, KANSAS
Character of Well (completed as Oil, Gas or Dry Hole) DRY HOLE
Date well completed NOVEMBER 24 19 67
Application for plugging filed NOVEMBER 24 19 67
Application for plugging approved NOVEMBER 24 19 67
Plugging commenced NOVEMBER 24 19 67
Plugging completed NOVEMBER 24 19 67
Reason for abandonment of well or producing formation NO PRODUCIBLE ZONE

If a producing well is abandoned, date of last production. NONE 10
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well EDGAR J. EVES
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4711 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	533'	NONE

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

MUD TO 800', FOLLOWED BY WOODEN PLUG, PLACED 100 SACKS CEMENT ON TOP OF PLUG.
MUD TO 40', FOLLOWED BY WOODEN PLUG, PLACED 1/2 SACK HULLS AND 10 SACKS CEMENT ON TOP OF PLUG TO BASE OF WELL CELLAR.

RECEIVED
STATE CORPORATION COMMISSION

DEC 13 1967

12-13-67

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor GARVEY DRILLING COMPANY
Address R.R. #2, GREAT BEND, KANSAS

STATE OF KANSAS, COUNTY OF BARTON, ss.
MONTE CHADD (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. MONTE CHADD, DIST. PROD. SUPT.

(Signature) *Monte Chadd*
R.R. #2, GREAT BEND, KANSAS
(Address)

SUBSCRIBED AND SWORN to before me this 11 day of DECEMBER, 19 67

Richard H. Dumbler
Notary Public.

My commission expires MAY 28, 1969

WELL LOG

COMPANY Petroleum, Inc.

SEC. 23 T. 22S R. 24W

FARM Springer

NO. 4

LOC. SW NW


TOTAL DEPTH 4711'

COUNTY Hodgeman

COMM. 11-10-67

COMP. 11-24-67

CONTRACTOR Garvey Drilling Company



CASING 8 5/8" @ 533' w/250 sx

ELEVATION 2426 KB

PRODUCTION D & A

FIGURES INDICATE BOTTOM OF FORMATIONS

- 192' Post Rock
- 800' Shale
- 1020' Red Bed and Shale
- 1055' Anhydrite
- 1435' Shale
- 1600' Shale and Shells
- 1680' Shale and Lime
- 2255' Shale and Shells
- 2415' Shale and Lime
- 3230' Lime and Shale
- 3425' Shale and Lime
- 4065' Lime and Shale
- 4152' Lime
- 4193' Lime and Shale
- 4230' Lime
- 4280' Lime and Shale
- 4485' Lime
- 4545' Lime and Shale
- 4634' Lime
- 4647' Chert and Lime
- 4653' Dolomite and Shale
- 4670' Chert
- 4711' Chert and Lime
- 4711' RTD

RECEIVED
 STATE CORPORATION COMMISSION
 DEC 13 1967
 CONSERVATION DIVISION
 Wichita, Kansas

State of Kansas
 County of Barton } ss

I, Sam N. Stephens of Garvey Drilling Company
 upon oath state the above and foregoing is a true and correct copy of the log of the Springer No. 4 well.

Sam N. Stephens

Subscribed and sworn to before me this 7th day of December 1967

My Commission Expires: November 5th, 1969

Richard D. Bay
 NOTARY PUBLIC