

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

HODGEMAN County, Sec. 23 Twp. 22S Rge. 24W (#) (W) X

Location as "NE/CNW/SW" or footage from lines APPROX. C-SE-SW

Lease Owner PETROLEUM, INC.

Lease Name SPRINGER Well No. 3

Office Address ROUTE 2, GREAT BEND, KANSAS

Character of Well (completed as Oil, Gas or Dry Hole) DRY HOLE

Date well completed MAY 10, 19 62

Application for plugging filed MAY 10, 19 62

Application for plugging approved MAY 10, 19 62


Plugging commenced MAY 10, 19 62

Plugging completed MAY 10, 19 62

Reason for abandonment of well or producing formation NO PRODUCIBLE ZONES

If a producing well is abandoned, date of last production NONE 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well W. L. LACKAMP, JR.

Producing formation ----- Depth to top ----- Bottom ----- Total Depth of Well 4715 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	436'	NONE

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

MUDDED UP WITH HEAVY MUD TO 400' FOLLOWED BY WOODEN PLUG, AND 1/4 SACK HULLS. PLACED 30 SACKS CEMENT THROUGH DRILL PIPE ONTO HULLS. MUDDED UP WITH HEAVY MUD TO 35' FOLLOWED BY WOODEN PLUG, 1/4 SACK HULLS AND 10 SACKS CEMENT TO BASE OF WELL CELLAR.

RECEIVED
STATE CORPORATION COMMISSION

JUN 1 1962

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor GARVEY DRILLING COMPANY
Address ROUTE 2, GREAT BEND, KANSAS

STATE OF KANSAS, COUNTY OF BARTON, ss.
DON SEARLE (employee of owner) or (XXXXXX XXXXXX) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. DON SEARLE, DIST. PROD. SUPT.

(Signature) Don Searle
ROUTE 2, GREAT BEND, KANSAS
(Address)

SUBSCRIBED AND SWORN to before me this 31st day of MAY, 19 62

My commission expires APRIL 14, 1963.

Arthur J. Nale
Notary Public.



WELL LOG

15-083-00076-0000

COMPANY PETROLEUM, INCORPORATED

SEC. 23 T. 22S R. 24W

FARM SPRINGER

NO. 3

LOC. C-SE, SW

TOTAL DEPTH 4715'


COUNTY HODGEMAN CO., KANSAS

COMM. April 28, 1962

COMP. May 10, 1962

CONTRACTOR

GARVEY DRILLING COMPANY



CASING 8-5/8" @ 436' w/250 sax.

ELEVATION 2433' D.F.

PRODUCTION D & A

FIGURES INDICATE BOTTOM OF FORMATIONS

405	Clay & shale
437	Shale
1150	Shale & red bed
1345	Sand
1652	Shale
1695	Anhydrite
1845	Shale & shells
2655	Shale & lime
2755	Lime
2970	Lime & shale
3595	Shale & lime
3765	Shale & lime w/chalk streaks
3975	Lime & shale w/chalk streaks
4140	Lime & shale
4700	Lime
4715	Chert & lime
4715	T. D.

RECEIVED
 STATE CORPORATION COMMISSION
 JUN 1 1962
 CONSERVATION DIVISION
 Wichita, Kansas

State of KANSAS }
 County of BARTON } SS

I, VERNE A. MORRIS of GARVEY DRILLING COMPANY

upon oath state the above and foregoing is a true and correct copy of the log of the #3 SPRINGER well.

Subscribed and sworn to before me this 29th day of May 1962

My Commission Expires: April 14, 1963

Verne A. Morris

Arthur J. Miles

 NOTARY PUBLIC