

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room **RECEIVED**
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-055-21520-00-01

LEASE NAME Six M Farms

MAY 08 2003
KCC WICHITA

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 1-23

1650 Ft. from S Section Line

3280 Ft. from E Section Line

SEC. 23 TWP. 22 RGE. 34 (E) or (W)

COUNTY Finney

Date Well Completed 02/10/1997

Plugging Commenced 04/03/2003

Plugging Completed 04/15/2003

LEASE OPERATOR Lario Oil & Gas Company

ADDRESS 301 S. Market Street; Wichita, KS 67202

PHONE#() 316-265-5611 OPERATORS LICENSE NO. 5214

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 04/15/03 - 12/09/02 (date)

by Kevin Stube (witness) - Steve Middleton (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing Formation Morrow Depth to Top 4744 Bottom 4750 T.D. 4940

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Surface		0	1845	8-5/8"	1845	None
Production		0	4940	5-1/2"	4940	1877'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set

CIBP @ 4690' w/2 sx cmt; 1st Plug: 50 sx cement + 15 sks ael @ 1870'. 2nd Plug: 40 sx @ 1000'

Top Plug: 10 sx @ surface. Cement is 60/40 Pozmix + 6% ael. Pumped down 5-1/2" csg.

Name of Plugging Contractor Allied Cementing Co., Inc. License No. _____

Address PO Box 368 Medicine Lodge, KS 67104-0368

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Lario Oil & Gas Company

STATE OF Kansas COUNTY OF Sedgwick, ss.

Jay G. Schweikert, Operations Engineer (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Jay G. Schweikert

(Address) 301 S. Market Street; Wichita, KS 67202

SUBSCRIBED AND SWORN TO
KATHY L. FORD
Notary Public - State of Kansas
My Appt. Expires 10-22-06

before me this 7th day of May, 2003

Kathy L. Ford
Notary Public

My Commission Expires: 10-22-06

BW

ALLIED CEMENTING CO., INC.

P.O. BOX 31
 RUSSELL, KS 67665
 PH. (785) 483-3887
 FAX (785) 483-5566
 FEDERAL TAX ID# 48-0727860

15-055-21520-0001

RECEIVED

INVOICE

MAY 08 2003

KCC WICHITA Invoice Number: 089703

Invoice Date: 04/16/03

Sold Lario Oil & Gas Company
 To: P. O. Box 784
 Hays, KS
 67601

Cust I.D.....: Lario
 P.O. Number.....: 6 M Farms #1 (PA well)
 P.O. Date.....: 04/16/03

Due Date.: 05/16/03
 Terms.....: Net 30

Item I.D./Desc.	Qty. Used	Unit	Price	Net	TX
Common	60.00	SKS	8.3500	501.00	T
Pozmix	40.00	SKS	3.8000	152.00	T
Gel	20.00	SKS	10.0000	200.00	T
Handling	100.00	SKS	1.1500	115.00	T
Mileage (75)	75.00	MILE	5.0000	375.00	T
100 sks @\$.05 per sk per mi					
Plug	1.00	JOB	475.0000	475.00	T
Mileage pmp tkr	75.00	MILE	3.5000	262.50	T

All Prices Are Net, Payable 30 Days Following
 Date of Invoice. 1 1/2% Charged Thereafter.
 If Account CURRENT take Discount of \$208.05
 ONLY if paid within 30 days from Invoice Date

Subtotal:	2080.50
Tax.....:	131.08
Payments:	0.00
Total...:	2211.58

Jim Dilligly
 4-30-03

Acct.	Expl.	File	OK to Pay
			<i>[Signature]</i>
MAY 2 2003			
HY	JS	KF	GV SF DM
PV	<i>xc</i>		
OD			