

STATE OF KANSAS
STATE CORPORATION COMMISSION


Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Hodgeman County, Sec. 17 Twp. 22 Rge. 24W (E) (W)

Location as "NE/CNW/SW" or footage from lines SW SW
Lease Owner Chief Drilling Co., Inc.
Lease Name Schauvliege Well No. #1
Office Address Suite 905 Century Plaza, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry hole
Date well completed November 28, 1969 19
Application for plugging filed November 28, 1969 19
Application for plugging approved November 28, 1969 19
Plugging commenced November 28, 1969 19
Plugging completed November 28, 1969 19
Reason for abandonment of well or producing formation Dry hole



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Edgar J. Eves, Sublette, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4710 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	257'	8 5/8"		

RECEIVED
STATE CORPORATION COMMISSION
DEC 2 1969
CONSERVATION DIVISION
Wichita, Kansas

12-2-69

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged through drill pipe @ 800' w/80 sacks cement
Plugged through drill pipe @ 250' w/30 sacks cement
Plugged through drill pipe @ 40' w/15 sacks cement

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Chief Drilling Co., Inc.
Address _____

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Jim Robinson (employee of owner) or ~~owner or operator~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Jim Robinson
Suite 905 Century Plaza, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 1st day of December, 1969

My commission expires May 9, 1971
Betty Brandt Notary Public

WELL LOG

Chief Drilling Co., Inc.
Suite 905 Century Plaza
Wichita, Kansas 67202

#1 SCHAUVLIEGE
SW SW of 17-22-24W
Hodgeman County

Contractor: Chief Drilling Co., Inc.

Commenced: 11-17-69
Completed: 11-28-69

Casing Record: 257' of 8 5/8" w/175 sacks Sunset cement.

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>ELEVATION</u>
Clay	0	60	2493 Gr.
Shale	60	257	2495 D.F.
Shale & sand	257	597	2498 K.B.
Shale, shell & sand	597	1680	
Anhydrite	1680	1713	
Shale & shell	1713	2182	
Shale & lime	2182	2735	
Lime	2735	2850	
Shale & lime	2850	4291	
Lime	4291	4355	
Lime & shale	4355	4475	
Lime	4475	4517	
Lime & shale	4517	4575	
Lime	4575	4630	
Chert	4630	4654	
Cherty lime	4654	4710	
Total depth	4710		

<u>FORMATION TOPS</u>	<u>ELEVATION</u>
Anhydrite	1680 + 818
Heebner	1713 + 785
Toronto	3941 -1443
Lansing	3961 -1463
Base K.C.	3994 -1496
Marmaton	4399 -1901
Pawnee Shale	4419 -1921
Marker	4492 -1994
Ft. Scott	4535 -2037
Mississippian	4658 -2139
Miss. Dolomite	4658 -2160
RTD	4710 -2212

RECEIVED
STATE CORPORATION COMMISSION
DEC 4 1969
CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK) ss:

I hereby certify that the above is a true and correct copy of the Driller's Log of the well drilled in the SW SW of Section 17-22-24W, Hodgeman County, Kansas, to the best of my knowledge and belief.

CHIEF DRILLING CO., INC.

Jim Robinson
Jim Robinson, Office Mgr.

Subscribed and sworn to before me this 2nd day of December, 1969.

Betty Brandt
Betty Brandt, Notary Public

MY COMMISSION EXPIRES:
May 9, 1971