

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Bldg  
Wichita, Kansas 67202

Form CP-4  
Rev. 12-15-80

15-083-21008-0000

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit

COUNTY Hodgeman SEC. 17 TWP. 22S RGE. 24 E/W  
Location as in quarters or footage from lines:  
760' FSL & 330' FWL SW/4

|  |  |  |  |
|--|--|--|--|
|  |  |  |  |
|  |  |  |  |
|  |  |  |  |
|  |  |  |  |

Lease Owner Viking Resources  
Lease Name Abbott Well No. #1  
Office Address 217 E. William Wichita, Ks. 67202  
Character of Well (Completed as Oil, Gas or Dry Hole): Dry  
Date Well Completed 11-7-82  
Application for plugging filed 11-7-82  
Plugging commenced 11-7-82  
Plugging completed 11-7-82  
Reason for abandonment of well or producing formation \_\_\_\_\_

Locate Well  
correctly on above  
Section Platt.

Was permission obtained from the Conservation Division or it's  
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Clarence Thomas, Jr.

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom \_\_\_\_\_ T.D. 4673'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

| Formation | Content | From | To | Size   | Put in | Pulled Out |
|-----------|---------|------|----|--------|--------|------------|
|           |         |      |    | 8 5/8" | 657'   | NONE       |
|           |         |      |    |        |        |            |
|           |         |      |    |        |        |            |
|           |         |      |    |        |        |            |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Spotted 70 sx. cement thru drill pipe @ 1070'.

Spotted 40 sx. cement thur drill pipe @ 350'.

Spotted 10 sx. cement in rathole.

Spotted 10 sx. cement and solid bridge - plug @ 40'.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor White & Ellis Drilling, Inc.

401 E. Douglas, Suite 500, Wichita, Ks. 67202

STATE OF Kansas COUNTY OF Sedgwick, ss.

Ernest Sifford (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.


(Signature) Ernest Sifford

401 E. Douglas #500 Wichita,  
(Address) Ks. 67202

SUBSCRIBED AND SWORN TO before me this 17th day of December, 1982


Carolyn J. Tjaden  
Carolyn J. Tjaden Notary Public.  
STATE CORPORATION COMMISSION

My Commission expires:



DEC 08 1982

CONSERVATION DIVISION  
Wichita, Kansas



15-083-21008-0000

WHITE

AND ELLIS DRILLING, Inc.

## DRILLERS LOG

OPERATOR: Viking Resources 217 E. William Wichita, Ks. 67202

CONTRACTOR: White & Ellis Drilling, Inc., 401 E. Douglas, Suite 500,  
Wichita, Ks. 67202Lease Name Abbott Well No. #1Sec. 17 T. 22S R. 24W Spot 760' FSL & 330' FWL SW/4County Hodgeman State Kansas Elevation 

## Casing Record:

Surface: 8 5/8" @ 657' with 320 sx.Production:  @  with  sx.Type Well: D & A Total Depth 4673'Drilling Commenced 10-30-82 Drilling Completed 11-7-82

| Formation   | From | To   | Tops |
|-------------|------|------|------|
| Cellar      | 0    | 7    |      |
| Shale       | 7    | 1079 |      |
| Anhydrite   | 1079 | 1094 |      |
| Shale       | 1094 | 1577 |      |
| Shale, Sand | 1577 | 1582 |      |
| Shale, Lime | 1582 | 3800 |      |
| Lime, Shale | 3800 | 4020 |      |
| Shale, Lime | 4020 | 4310 |      |
| Lime        | 4310 | 4430 |      |
| Shale, Lime | 4430 | 4525 |      |
| Lime        | 4525 | 4620 |      |
| Shale, Lime | 4620 | 4673 |      |

RECEIVED  
STATE CORPORATION COMMISSION

DEC 08 1982

CONSERVATION DIVISION  
Wichita, Kansas