

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Hodgeman SEC. 12 TWP. 22S RGE. 24W E/W
Location as in quarters or footage from lines:
C NW NW

Locate Well
correctly on above
Section Platt.

Lease Owner Rains & Williamson Oil Company, Inc.
Lease Name Blount A-1 Well No. _____
Office Address 435 Page Court Bldg. 220 W. Douglas Wichita, Ks 67202
Character of Well (Completed as Oil, Gas or Dry Hole): _____
Date Well Completed _____
Application for plugging filed _____
Plugging commenced 12-4-81
Plugging completed 12-18-81
Reason for abandonment of well or producing formation Depelting

Was permission obtained from the Conservation Division or it's Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Steve Durant

Producing formation _____ Depth to top _____ bottom _____ T.D. 4750'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8-5/8"	595'	none
				4-1/2"	4748'	2301'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged off bottom with sand to 4600' and set 4 sacks cement. Shot and worked pipe @3910', 3618', 3207', 3014', 2882', 2718', 2515', 2431' and 2311'. Pulled a total of 58 joints of pipe. Squeezed hole with 7 sacks gel, 3 sacks hulls, 8 sacks gel, 70 sacks cement, 10 sacks gel, released plug and displaced with 1 sack hulls and 70 sacks cement. Plugging Completed.

12-22-81

RECEIVED
STATE CORPORATION COMMISSION

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Kelso Casing Pulling DEC 22 1981

CONSERVATION DIVISION
Wichita Kansas

STATE OF Kansas COUNTY OF Rice, ss.
R. Darrell Kelso (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso
Chase, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 21st. day of December, 19 81

My Commission expires: 

Notary Public.

DRILLER'S LOG

COMPANY: Rains & Williamson Oil Co., Inc.

SEC. 12 T. 22S R. 24W

WELL NAME: Blount "A" #1

LOC. C NW NW

COUNTY: Hodgeman

RIG NO. #2

TOTAL DEPTH 4750'

ELEVATION 2431 GL 2440 KB

COMMENCED: 12-27-80 COMPLETED: 1-7-81

CONTRACTOR: Rains & Williamson Oil Co., Inc.

CASING RECORD:

SURFACE: 8 5/8" @ 595' w/200 sx. 50/50 poz., 2% gel, 3% cc. and 100 sx. common, 3% cc., 2% gel.

PRODUCTION: 4 1/2" @ 4748' w/150 sx. common.

LOG

(Figures Indicate Bottom of Formations)

Shale	1983
Shale & Sand	2304
Shale & Lime	3823
Lime & Shale	4440
Shale & Lime	4445
Lime	4750
<u>ROTARY TOTAL DEPTH</u>	<u>4750</u>

RECEIVED
STATE CORPORATION COMMISSION
SEP 18 1981
CONSERVATION DIVISION
Wichita, Kansas

STATE OF Kansas)

COUNTY OF Sedgwick)

SS:

I, Wilson Rains, President of Rains & Williamson Oil Co., Inc.

upon oath state that the above and foregoing is a true and correct copy of the log of the

Blount "A" #1 well.

Wilson Rains
Wilson Rains

Subscribed and sworn to before me this 28 day of January, 1981.

My Appointment Expires:

10-4-83

Juanita M. Green
Juanita M. Green

