


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Hodgeman County, Sec. 12 Twp. 22S Rge. 24 ~~NE~~/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines _____
C SW NE
Lease Owner Euwer Petroleum Company
Lease Name Blount Well No. #1
Office Address 110 N. Market - Suite 206, Wichita, Ks. 67202
Character of Well (Completed as Oil, Gas or Dry Hole) _____



Locate well correctly on above
Section Plot

Dry Hole
Date Well completed 5-6-78 19
Application for plugging filed 5-6-78 19
Application for plugging approved 5-6-78 19
Plugging commenced 5-6-78 19
Plugging completed 5-6-78 19
Reason for abandonment of well or producing formation
Commercial quantities of oil not found
If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Clarence Thomas, Jr.
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4730'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	599'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid
was placed and the method or methods used in introducing it into the hold. If cement or other
plugs were used, state the character of same and depth placed, from _____ feet to
_____ feet for each plug set.

STATE CORPORATION COMMISSION

MAY 22 1978
5-22-78
CONSERVATION DIVISION
Wichita, Kansas

Plug @ 900' w/60 sx.
Plug @ 600' w/35 sx.
Plug @ 40' w/10 sx.
Rat Hole 5 sx.


(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Rains & Williamson Oil Co., Inc.

STATE OF Kansas COUNTY OF Sedgwick, ss.
Wilson Rains, President of Rains & Williamson Oil Co., Inc. (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of
the facts, statements, and matters herein contained and the log of the above-described well
as filed and that the same are true and correct. So help me God.

(Signature) Wilson Rains
435 Page Court, 220 W. Douglas, Wichita, Ks. 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 9 day of May, 1978
My commission expires 10-4-79
Juanita M. Green
Notary Public.



DRILLER'S LOG

COMPANY: Euwer Petroleum Company

SEC. 12 T. 22S R. 24W

WELL NAME: Blount #1

LOC. C SW NE

RIG NO. #7

COUNTY: Hodgeman

TOTAL DEPTH 4730'

ELEVATION

COMMENCED: 4-26-78

COMPLETED: 5-6-78

CONTRACTOR: Rains & Williamson Oil Co., Inc.

CASING RECORD:

SURFACE: 8 5/8" @ 599' w/300 sx. 60/40 poz., 2% gel, 3% cc.

PRODUCTION: D&A

LOG

(Figures Indicate Bottom of Formations)

Sand & Shale	603
Shale & Shells	1097
Sand & Shale	1700
Shale	2045
Lime & Shale	2505
Shale	2625
Lime & Shale	3593
Shale & Lime	3803
Lime & Shale	3990
Lime	4125
Lime & Shale	4245
Lime	4498
Lime & Shale	4584
Lime	4730
<u>ROTARY TOTAL DEPTH</u>	<u>4730</u>

RECEIVED
STATE CORPORATION COMMISSION

MAY 22 1978

CONSERVATION DIVISION
Wichita, Kansas

STATE OF Kansas)

COUNTY OF Sedgwick)

SS:

I, Wilson Rains, President of Rains & Williamson Oil Co., Inc.

upon oath state that the above and foregoing is a true and correct copy of the log of the

Blount #1 well.

Wilson Rains
Wilson Rains



Subscribed and sworn to before me this 9 day of May, 1978.

My Appointment Expires:
10-4-79

Juanita M. Green
Juanita M. Green