

STATE OF KANSAS
NATURAL RESOURCES COMMISSION
1001 S. Market, Room 2078
Topeka, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-075-20185-0000

LEASE NAME Allen ^{Alan} (HCU)

WELL NUMBER 1 (820)

JUL 20 2001

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

660 Ft. from (S) Section Line

1980 Ft. from (E) Section Line

SEC. 8 TWP. 22 RGE. 40 (or (W))

CONSERVATION DIVISION

LEASE OPERATOR Louis Dreyfus

ADDRESS 14000 Quail Spgs Parkway - Okla City OK 73134 COUNTY Hamilton

PHONE (405) 749-1300 OPERATORS LICENSE NO. 31321

Date Well Completed 11-18-64

Character of Well _____

Plugging Commenced 6-7-01

Well, (Gas) O&A, SWO, Input, Water Supply Well

Plugging Completed 6-7-01

A plugging proposal was approved on 6-6-01 (date)

Kevin Strube (KCC District Agent's Name)

ACQ-1 filed? Yes If not, is well log attached? _____

Producing Formation Winfield Depth to Top 2706 Bottom 2718' T.O. 2765

Show depth and thickness of all water, oil and gas formations.

WELL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				<u>8 3/8</u>	<u>342</u>	<u>—</u>
				<u>4 1/2</u>	<u>2760</u>	<u>—</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug material used, state the character of same and depth placed, from _____ feet to _____ feet each so
Mixed 1 SK hulls & 20 SK cmt. to plug perfs from 2706 to 2506 - pumped mud to 1200 - mixed 20 SK 1200 to 900 - mud to 400 - 30 SK 400 to 0 mixed 10 SK down 8 3/8 - 4 1/2 annulus 40 to 0. Cut off 8 3/8 & 4 1/2 & capped 8 3/8 3 ft. below G.L.

Name of Plugging Contractor SARGENT AND HORTON PLUGGING, INC. License No. 31151

Address Route 1, Box 49BA Tyrone, OK 73951-9731 (580) 854-6515

Name of Party Responsible for Plugging Fees: Louis Dreyfus Natural Gas Corp

State of Okla. County of Okla., ss.

Lenora Sawyer (Employee of Operator) or (Operator)


above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and statements herein contained and the log of the above-described well as filed thereon and the same are true and correct, so help me God.

(Signature) Lenora Sawyer

(Address) 14000 Quail Spgs Parkway

Subscribed and sworn to before me this 18th day of July, 2001

Lorrie A. Renfro
Notary Public



OR