


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Hodgeman County, Sec. 9 Twp. 22S Rge. (E) 21 (W)
Location as "NE/CNW&SW¼" or footage from lines C/NW SE
Lease Owner Thunderbird Drilling, Inc.
Lease Name Malone Well No. 1
Office Address P. O. Box 18407, 4328 East Kellogg, Wichita, Kansas 67218
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed February 2 19 72
Application for plugging filed February 2 19 72
Application for plugging approved February 2 19 72
Plugging commenced February 2 19 72
Plugging completed February 2 19 72
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Edgar J. Eves, Sublette, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4368 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	8-5/8"	0	368.75			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.
Plugged as follows: Plugged at 850' to 550' with 80 sacks of common cement; plugged at 350' to 250' with 30 sacks of common cement; plugged at 45' with 15 sacks of common cement. Plug down at 4:30 P. M. February 2, 1972.

RECEIVED
STATE CORPORATION COMMISSION
FEB 14 1972
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Strata Drilling, Inc.
Address P. O. Box 355, Great Bend, Kansas 67530


STATE OF KANSAS, COUNTY OF BARTON, ss.
Charles W. Steincamp (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Charles W. Steincamp
Charles W. Steincamp, President
P. O. Box 355, Great Bend, Kansas 67530
(Address)

SUBSCRIBED AND SWORN TO before me this 9th day of February, 19 72

My commission expires September 14, 1973

Elaine H. Taylor
Elaine H. Taylor Notary Public.



D R I L L E R S L O G

#1 Malone

CASING RECORD: 362.75' of used 8-5/8" surface casing.	COMPANY: Thunderbird Drilling, Inc.	DESCRIPTION: C/NW SE Section 9-22S-21W Hodgeman County, Kansas
	CONTRACTOR: Strata Drilling, Inc.	
TOTAL DEPTH: 4368'	COMMENCED: January 22, 1972	
	COMPLETED: February 2, 1972	

D. & A.

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Top Soil, Clay & Blue Shale	0	399	Ran 362.75' of used 8-5/8" surface casing; set and cemented at 368.75' with 200 sacks of common cement, 2% gel and 3% C. C. Plug down at 4:15 P. M. January 23, 1972.
Shale	399	635	
#1 Anhydrite	635	642	
Sand	642	880	
Red Bed, Shale & Shells	880	1284	
#2 Anhydrite	1284	1313	
Red Bed, Shale & Shells	1313	1319	
Shell Rock, Red Bed, Shale & Salt	1319	1641	
Red Bed, Shale & Salt	1641	1945	
Shale, Broken Lime & Lime	1945	2022	
Lime & Shale	2022	3269	
Lime w/Shale Streaks	3269	3715	
Shale & Lime	3715	4144	
Lime	4144	4346	
Lime & Chert	4346	4354	
Lime	4354	4362	
Chert, Shale & Lime	4362	4368	

Rotary Total Depth 4368'

D. & A.

Plugged as follows: Plugged at 850' to 550' with 80 sacks of common cement, plugged at 350' to 250' with 30 sacks of common cement; plugged at 45' with 15 sacks of common cement. Plug down at 4:30 P. M. February 2, 1972.

RECEIVED
STATE CORPORATION COMMISSION
FEB 14 1972
CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS)
) ss.
COUNTY OF BARTON)

I certify that this is a true and correct copy of the above log to the best of my knowledge.

STRATA DRILLING, INC.

Charles W. Steincamp
Charles W. Steincamp, President

Subscribed and sworn to before me this 9th day of February, 1972.

My Commission Expires:

December 1973

Elaine H. Taylor
Elaine H. Taylor, Notary Public

