


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Hodgeman County, Sec. 5 Twp. 22S Rge. 21 (W)

Location as "NE/CNW/SW" or footage from lines: C NE SW

Lease Owner: Pickrell Drilling Company

Lease Name: Dovel "A" Well No. 1

Office Address: 705 Fourth National Bank Bldg., Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole): Dry Hole

Date well completed: February 8 1970

Application for plugging filed: February 8 1970

Application for plugging approved: February 8 1970

Plugging commenced: February 8 1970

Plugging completed: February 8 1970

Reason for abandonment of well or producing formation: Dry Hole

If a producing well is abandoned, date of last production: 19__

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well: Edgar J. Eves

Producing formation: Depth to top: Bottom: Total Depth of Well: 4384 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	281'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Bottom Plug @ 840' w/80 sacks cement, Plug @ 295' w/30 sacks cement, Top Plug @ 60' w/15 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION
FEB 13 1970
CONSERVATION DIVISION
Wichita, Kansas


(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor: Pickrell Drilling Company
Address: 705 Fourth National Bank Building, Wichita, Kansas 67202

STATE OF Kansas, COUNTY OF Sedgwick, ss.
C. W. Sebitts (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. W. Sebitts
705 Fourth National Bank Bldg., Wichita, Kansas (Address)

Subscribed and sworn to before me this 12th day of February, 1970

Esther Lamone
Notary Public.



COMPANY: Pickrell Drilling Company
705 Fourth National Bank Building
Wichita, Kansas 67202

Rotary Drilling Commenced 1/28/70

Rotary Drilling Completed 2/8/70

LOCATION: Dovel "A" No. 1, C NE SW Section 5-22S-21W,
Hodgeman County, Kansas

CONTRACTOR: PICKRELL DRILLING COMPANY
Wichita, Kansas

CASING RECORD: Run 14 Jts. 8-5/8" surface casing set @ 281'K.B. Cemented w/170
sacks. Completed 7 P.M. January 28, 1970. Circulated.
No.oil string run. D & A Plugged February 8, 1970.

LOG

(Figures indicate bottom of formation — measurements from top of rotary bushing.)

115	Sand		<u>C.F.S.</u>
281	Shale & Shells		4155
660	Shale & Red Beds		4170
740	Shale		4310
945	Sand		4332
1075	Shale & Sand Stringers		4362
1295	Anhydrite		4372
1450	Shale & Lime		4384
1685	Lime & Shale		
2135	Shale		
2180	Shale & Lime		
2275	Lime & Shale		<u>S.L.M.</u>
2390	Shale & Lime	Board	3859.53
2520	Lime & Shale	Strap	3858.85
2665	Shale & Lime		.68 Difference
2755	Lime & Shale		
3340	Shale		
3530	Shale & Sandy Lime		<u>Slope Tests</u>
3710	Sandy Lime & Shale		2000
3905	Lime & Shale		2500
3995	Shale & Lime		3000
4115	Lime & Shale		3500
4180	Shale & Lime		4000
4372	Lime		
4384	Mississippian, RTD		

RECEIVED
STATE CORPORATION COMMISSION
FEB 13 1970
CONSERVATION DIVISION
Wichita, Kansas

The undersigned, C. W. Sebitts, Attorney-in-Fact for PICKRELL DRILLING COMPANY, hereby certifies in behalf of said Company, that the above is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

PICKRELL DRILLING COMPANY
By [Signature]
C. W. Sebitts Attorney-in-Fact

STATE OF KANSAS }
COUNTY OF SEDGWICK } ss.:

On this 12th day of February, 1970, before me the undersigned, a Notary Public, in and for

County of Sedgewick, Kansas, the above said, personally appeared C. W. Sebitts, to me known to be the person who subscribed the name of PICKRELL DRILLING COMPANY to the foregoing instrument as its Attorney-in-Fact and acknowledged to me that he executed the same as his free and voluntary act and deed, and that he is duly authorized to execute the same as his free and voluntary act and deed, for the uses and purposes therein set forth.

Given under my hand and seal of office the day and year last above written.



My commission expires January 19, 1973

Esther Lamone
Notary Public