

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

Hodgeman County, Sec. 1 Twp. 22S Rge. (E) 21(W)

Location as "NE/CNW/SW" or footage from lines C SW NW

Lease Owner Rains & Williamson Oil Co.

Lease Name RUCKER Well No. 1

Office Address 1425 Wichita Plaza, Wichita 2, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed May 26 19 64

Application for plugging filed May 26 19 64

Application for plugging approved May 26 19 64


Plugging commenced May 26 19 64

Plugging completed May 26 19 64

Reason for abandonment of well or producing formation No oil or gas found  
in commercial quantities.

If a producing well is abandoned, date of last production - - 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above  
Section Plat

Name of Conservation Agent who supervised plugging of this well Hugh Scott, Sublette, Kansas

Producing formation - - Depth to top - - Bottom - - Total Depth of Well 4479 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	337'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Set plug @ 700', spot with 25 sacks cement. Mud back to 337', set plug and hulls and spot with 25 sacks cement. Mud back to 45', set plug and hulls. Capped with 15 sacks cement.

RECEIVED  
STATE CORPORATION COMMISSION

MAY 28 1964

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Rains & Williamson Oil Co.

Address 1425 Wichita Plaza Building, Wichita 2, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

Wilson Rains

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Rains & Williamson Oil Co.  
Address 1425 Wichita Plaza Building, Wichita 2, Kansas

(Signature)

Wilson Rains, Partner  
1425 Wichita Plaza, Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN to before me this 27th day of May, 19 64

My commission expires 1-8-68

Shirley Keck, Notary Public.

## ROTARY DRILLING LOG

Operator: Rains & Williamson Oil Co.  
 No. 1 RUCKER  
 C SW NW Section 1-22S-21W  
 Hodgeman County, Kansas

Contractor: Rains & Williamson Oil Co.  
 Comm: May 14, 1964  
 Comp: May 26, 1964

Remarks: set 337' of 8-5/8" surface casing, w/175 sx GL3 cement

## Formations:

Surface	.74'
Sand	85'
Shale	337'
Shale & Shells	540'
Anhydrite	616'
Shale & Red Bed	700'
Dakota Sand	840'
Shale & Red Bed	1195'
Anhydrite	1296'
Shale	1530'
Shale & Shells	1810'
Lime & Shale	2130'
Lime & Chert	4348'
Lime, Shale & Chert	4405'
Chert & Lime	4445'
Lime, shale & chert	4479'
Rotary Total Depth (D&A)	4479'

**RECEIVED**  
 STATE CORPORATION COMMISSION

MAY 28 1964

CONSERVATION DIVISION  
 Wichita, Kansas

We certify the above log is true and correct to the best of our knowledge and belief.

RAINS & WILLIAMSON OIL CO.

*Wilson Rains*  
 Wilson Rains  
 Partner

Subscribed and sworn to before me, a Notary Public in and for the State of Kansas, County of Sedgwick, this 27th day of May, 1964.

My Commission Expires:  
 January 8, 1968

*Shirley Keck*  
 Shirley Keck Notary Public