


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
300 Bittling Building  
Wichita, Kansas

Pawnee County. Sec. 3 Twp. 22S Rge. 20 ( W) ( W)  
Location as "NE/CNW/SW" or footage from lines SE SE NW  
Lease Owner The Vickers Petroleum Co., Inc.  
Lease Name COLLEGE Well No. 1  
Office Address Box 2240, Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed November 14 1955  
Application for plugging filed November 15 1955  
Application for plugging approved November 15 1955  
Plugging commenced November 15 1955  
Plugging completed November 15 1955  
Reason for abandonment of well or producing formation Dry



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Warren H. Horner  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4771 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	585'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled hole with mud to 300'. Dumped 20 sx. cement @ 300' for plug.

Filled with mud to 35'. Dumped 10 sx. cement @ 35' for plug.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Harms - Burt Drilling Company  
Address Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
A. E. Collins (employee of owner) or (~~owner or operator~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) A. E. Collins  
Box 2240, Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 23rd day of November, 1955

Allen P. Denton

Notary Public.

My commission expires August 13, 1957

24-7988-5 3-53-20M

PLUGGING  
FILED SEC 3 TWP 22S RGE 20W  
BOOK PAGE 17 LINE 12

11-25-55  
CONSERVATION DIVISION  
Wichita, Kansas

## THE VICKERS PETROLEUM CO., INC.

College #1  
SE SE NW Sec. 3-22S-20W  
Pawnee County, Kansas

Casing Record:  
8 5/8" @ 585' w/375 sx

Commenced: Oct. 27, 1955  
Completed: Nov. 14, 1955

Elevation: 2161 R.B.  
D & A

LOG

Clay	0-92
Sand & clay streaks	92-169
Sand & clay	169-260
Sandy shale	260-525
Red beds	525-602
Wtr sand	602-623 (Flow 20 BWPB)
Blaine anhydrite	623-639
Red beds	639-731
Sand	731-859
Red beds	859-1293
Anhydrite	1293-1320
Shale & shells	1320-1734
Salt	1734-1947
Anhydrite & dolomite	1947-2255
Dolomite, lime & shale	2255-2398
Lime & shale	2398-3102
Shale	3102-3157
Lime & shale	3157-3727
Black shale	3727-3733
Shale & shells	3733-3796
Lime	3796-4203
Lime & shale	4203-4358
Chert	4358-4419
Sand & shale	4419-4448
Dolomite & lime	4448-4467
Dolomite	4467-4684
Sand & dolomite	4684-4715
Shale	4715-4739
Dolomite	4739-4771

DST #1 4362-70, op 1 1/2 H with steady very weak blow, rec 30' VSOCM, FP 20-30#, SIP 540#/1 H (still bldg).

DST #2 4362-85, op 1 H with very weak blo - - flushed tool & blew intermittently, rec 35' M with slight trace O, FP 30-40#, SIP 1120#/1 H (still bldg).

Rotary TD 4771.  
Schlumberger TD 4768.

Rotary Tops:

Heeb	3727
Lans	3796
Chat	4358
Kinder sh	4419
Kinder ss	4427
Viola dol ?	4467
Simp	4684
Arb	4739

I hereby certify that this Log is true and correct to the best of my knowledge and belief.

THE VICKERS PETROLEUM CO., INC.

BY *Lyle Thomas*

Subscribed and sworn to before me this 23 day of November, 1955.

*Allen J. Denton*  
Notary Public,  
STATE OF KANSAS

NOV 25 1955

My Commission expires August 13, 1957.

**PLUGGING** CONSERVATION DIVISION  
Wichita, Kansas  
FILE SEC 2-12220W  
BOOK PAGE 17 LINE 10