


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202

Pawnee County, Sec. 8 Twp. 22 Rge. 20 E/W  
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines \_\_\_\_\_  
SW SW NE  
Lease Owner Sterling Drilling Company  
Lease Name Sweeney "A" Well No. 1  
Office Address Sterling, Kansas 67579  
Character of Well (Completed as Oil, Gas or Dry Hole) \_\_\_\_\_



Locate well correctly on above Section Plat

Date Well completed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging filed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging approved \_\_\_\_\_ 19\_\_\_\_  
Plugging commenced 7/21/78 \_\_\_\_\_ 19\_\_\_\_  
Plugging completed 7/25/78 \_\_\_\_\_ 19\_\_\_\_  
Reason for abandonment of well or producing formation \_\_\_\_\_  
depleted.  
If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Massey  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4518  
Show depth and thickness of \_\_\_\_\_ water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	312	none
				5 1/2"	4518	3621

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Sanded to 4445' and ran 4 sacks cement. Shot pipe at 3617', pulled 93 joints of 5 1/2" casing. Pumped 25 sacks gel, plug, 2sacks hulls and 140 sacks posmix with 6% gel.

PLUGGING COMPLETE.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor KELSO CASING PULLING  
CHASE, KANSAS


STATE OF KANSAS COUNTY OF RICE, ss.  
R. DARRELL KELSO (employee of owner) or (owner or operator)  
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso  
CHASE, KANSAS

SUBSCRIBED AND SWORN TO before me this 28th day of July, 1978

Margaret Melcher  
Notary Public.

My commission expires \_\_\_\_\_



STERLING DRILLING COMPANY  
P. O. Box 129  
Sterling, Kansas 67579

TW70

WELL LOG ----- SWEENEY A-1  
Located: SW SW NE<sub>4</sub> Section 8-22S-20W, Pawnee County, Kansas

OWNER: Voyager Petroleum, Inc., Kansas-Nebraska Natural Gas Company, Inc.  
and Sterling Drilling Company

ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: February 10, 1975

COMPLETED: February 21, 1975

TOTAL DEPTH: 4520'

<u>LOG</u>	<u>CASING RECORD</u>
0 - 100 Clay and Post Rock	Ran 10 joints used 8 5/8" casing, 301' set at 312' K.P. with 225 sacks 60/40 Pozmix with 3% cc. Plug down at 7:45 PM, 2-10-75.
100 - 714 Shale	
714 - 725 Blane	
725 - 950 Shale and Sand	
950 - 2005 Shale and Shells	
2005 - 3265 Lime and Shale	
3265 - 3642 Lime	
3642 - 3770 Lime and Shale	
3770 - 4470 Lime	
4470 - 4520 Lime and Chert	Ran 122 joints 5 1/2", 15.5# 8rd casing, 4538.30' set at 4513' with 100 cu. ft. 50/50 salt saturated Pozmix with CRF-2, salt flush ahead cement. Plug down at 10:30 PM, 2-21-75.

RECEIVED  
STATE CORPORATION COMMISSION

JUN 07 1978

CONSERVATION DIVISION  
Wichita, Kansas