

KANSAS

Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 31 1978

J. Lewis Brock  
Administrator  
245 North Water  
Wichita, KS 67202

API Number 15-145-20359-0000 (of this well)

Operator's Full Name Sterling Drilling Co.

Complete Address Box 129, Sterling, Kansas 67579

Lease Name Sweeny "A" Well No. 1

Location SW SW NE Sec. 8 Twp. 22 Rge. (E) (W) 20

County Pawnee Total Depth 4520'

Abandoned Oil Well XX Gas Well        Input Well        SWD Well        D & A       

Other well as hereafter indicated       

Plugging Contractor Kelso Casing Pulling

Address Box 176, Chase, Kansas 67524 License No. 683

Operation Completed: Hour 2:30 P Day 25 Month 7 Year 1978

The above well was plugged as follows:

Total Depth 4520' 8 5/8 csg set 312' cwc 225 sk.

5 1/2 csg set 4518' cw 100 sk cem.

5 1/2 csg PBD 4494' & Perf. (4462'-4470')

Filled 5 1/2 csg W/sd(4494'-4445') dumped 4 sk cem W/dump bailer. (4445'-4415')

Cutoff & recovered 3617' of 5 1/2 csg.

Pumped down 8 5/8 csg with 25 sk gel & water W/200 lbs hulls, released 8 5/8 plug

& pumped 140 sk 50-50 poz 6% & shutin. FPP 750 lbs.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 7-31-78  
INV. NO. 7761-W

Signed: Leo Messer  
Well Plugging Supervisor