

Form CP-3
Rev. 6-26-62

Y
KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
NOV 9 1967

CONSERVATION DIVISION
WICHITA, KANSAS

11-9-67

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Leben Drilling, Inc.

Complete Address: 815 Wichita Plaza, Wichita, Kansas

Lease Name Springer "A" Well No. 1

Location 150 S C SE SE Sec. 24 Twp. 22 Rge. 24 (W)

County Hodgeman Total Depth 4620'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: None

Plugging Contractor: Leben Drilling, Inc.

Address: 815 Wichita Plaza, Wichita, Kansas License No. _____

Operation Completed: Hour 4:00AM Day 7 Month 11 Year 1967

The Above well was plugged as follows:

8 5/8" to 519' circulated w/ cement. Mud 4620' to 900'

Spotted 100 sacks cement 900' to 550' Mud 550' to 450'

Spotted 30 sacks cement 450' to 350' Mud 350' to 40'

Plug, Hulls & 10 sacks cment 40' to 0'

Sun Cementing Pump Truck.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *Edmund J. Evers*
Well Plugging Supervisor

DATE 11/9/67
INV. NO. 6654-W