

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

DEC 8 1966
12-8-66
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Pet-Ex Company, Inc., c/o Morrison Producing Company

Complete Address: P. O. Box 712, El Dorado, Kansas

Lease Name Swingle Well No. # C-1

Location C N/2 SW SE Sec. 25 Twp. 30 Rge. 9 (E) (W) W

County Kingman Total Depth 3222'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: This hole was a wash down.

Plugging Contractor: Knight Casing Pulling Company

Address: Box 405, Chase, Kansas License No. 436

Operation Completed: Hour 2:30PM Day 6th Month Dec. Year 1966

The Above well was plugged as follows:

409' of 8 5/8" surface pipe, cemented with 300 sacks. 3215' of 4 1/2"
long string, cemented with 300 sacks. Plug back T.D. 2510'. Top perforation
2446'. Bottom of the hole was sanded to 2425, and cemented with 3 sacks,
through the dump bailer. 1836' of 4 1/2" long string was recovered from the
hole. Fluid level in the hole was at 370', bridge plug and rock bridge
from 370' to 360', and cemented with 25 sacks. Hole was filled with mud
to 40', rock bridge from 40' to 30', and cemented with 10 sacks to the
base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 12/9/66

INV. NO. 4424-W