

*Y* KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
MAR 1 1967  
3-1-67  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name Petroleum, Inc.

Complete Address: 300 West Douglas, Wichita, Kansas

Lease Name Casebolt Well No. # 1

Location SW NW NE Sec. 33 Twp. 30 Rge. 9 (E) (W) W

County Kingman Total Depth 4407'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: \_\_\_\_\_

Plugging Contractor: Garvey Drilling Company

Address: R. R. # 2, Great Bend, Kansas License No. \_\_\_\_\_

Operation Completed: Hour 5:00PM Day 27th Month Feb. Year 1967

The Above well was plugged as follows:

249' of 8 5/8" surface pipe, cement circulated with 200 sacks. Hole  
was filled with drilling mud to 240', 1st cementing plug, bridged with  
with 2 sacks of dry cement and 1/2 sack of hulls, on fluid at 240', and  
cemented with 23 sacks. Hole was filled with drilling mud to 40', 2nd  
cementing plug, bridged with 1 sack of dry cement and 1/2 sack of hulls  
on fluid at 40', and cemented with 9 sacks to the base of the cellar.  
Rat hole bridged and cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 3/1/67  
INV. NO. 4845-W

Signed: Arlene Elving  
Well Plugging Supervisor