

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSIONJ. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, KansasMAY 1 1963
5-1-63
CONSERVATION DIVISION
Wichita, KansasOperator's Full Name Pickrell Drilling Co.Complete Address: 705 4th National Bank Bldg., Wichita, KansasLease Name Scarth Well No. # 1Location SE SE NW Sec. 33 Twp. 30 Rge. 9 (E) (W) WCounty Kingman Total Depth 4429Abandoned Oil Well Gas Well Input Well SWD Well D & A XOther well as hereafter indicated: Plugging Contractors: Forbes Casing PullingAddress: Box 221, Great Bend, Kansas License No. 49Operation Completed: Hour 4:00PM Day 26th Month April Year 1963

The Above well was plugged as follows:

232' of 8 5/8" surface pipe, cement circulated. 4428' of 4 1/2" long string,cemented with 115 sacks. Plugged back to 4398'. Perferated from 4351' to4361'. Sanded to 4340', cemented with 3 sacks. Hole was filled to 200',10' rock bridge, cemented with 20 sacks. Hole was filled with mud to40', 10' rock bridge, cemented with 10 sacks to base cellar.3815' of 4 1/2" long string recovered from hole.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 5/1/63INV. NO. 6991-4Signed: Arlene Elving

Well Plugging Supervisor