

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

RECEIVED  
STATE CORPORATION COMMISSION  
FEB 10 1972  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Petroleum Inc.

Complete Address 300 W. Douglas, Wichita, Kansas

Lease Name Schauvliege "B" Well No. 1

Location C NE NW Sec. 17 Twp. 22 Rge. 24 (~~25~~) (W)

County Hodgeman Total Depth 4710'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated None

Plugging Contractor Garvey Drilling Co.

Address Rt. 2, Great Bend, Kansas License No. \_\_\_\_\_

Operation Completed: Hour 12:30 AM Day 8 Month 2 Year 1972

The above well was plugged as follows:

8 5/8" to 596' circulated w/ cement. Mud 4710' to 600.

Spotted 70 sacks cement 600' to 350' Mud 350' to 45'

Plug, Hulls & 10 sacks cement 40' to 0'. Globe Cementing Pump Truck.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 2/11/72

INV. NO. 5153-W

Signed:   
Well Plugging Supervisor